


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Hamilton

County. Sec. 34 Twp. 24S Rge. 42W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NE SW

Lease Owner Earl F. Wakefield

Lease Name Barnett

Well No. 1-34

Office Address 515 Union Center Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 29 19 64

Application for plugging filed May 1 19 64

Application for plugging approved Verbal-John Roberts April 29 19 64

Plugging commenced April 29 19 64

Plugging completed April 29 19 64

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott

Producing formation Not Productive Depth to top Bottom Total Depth of Well 2470 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		Surface	113'	8 5/8"	113'	None Cmt Circ.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

The hole was drilled to a total depth of 2470 feet with drilling mud having a weight of 10.9#/gal, viscosity of 34, and water loss of 8.4 cc.

Plugs were spotted through drill pipe as follows:

1. 25 Sacks from 732 to 644'
2. 15 Sacks from 124 to 74'
3. A wooden plug was spotted at 28 feet and the casing was filled to surface with cement. The well was allowed to stand open for 16 hours and again filled to surface with cement (5 sacks). The casing was then cut off 3 feet below ground level and a cap welded over the 8 5/8" casing.

RECEIVED
STATE CORPORATION COMMISSION

5-7-64

MAY 7 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Earl F. Wakefield
Address 515 Union Center Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Earl F. Wakefield

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

515 Union Center Building, Wichita

(Address)

SUBSCRIBED AND SWORN to before me this 5th day of May, 19 64

My commission expires

January 25, 1965

Wanda W. Riley

Notary Public.

LEASE: BARNETT #1-34
 OWNER: EARL F. WAKEFIELD
 CONTRACTOR: EARL F. WAKEFIELD
 COMM: 4-25-64
 COMP: 4-29-64

LOCATION: NE SW
 SECTION 34-24S-42W
 HAMILTON COUNTY, KANSAS
 CASING: 8 5/8" Set @ 113'
 D & A @ 2470'

ELEVATION: 3470' K.B.

Surface Soil	40
Sand and Clay	60
Shale	85
Blue Shale	115
Shale and Anhydrite	685
Shale	800
Anhydrite	830
Red Bed and Sand	1030
Red Bed, Shale	1330
Salt	1490
Shale and Anhydrite	1685
Shale and Shells	1864
Anhydrite	1880
Shale - Lime	2235
Lime and Shale	2355
Lime	2470
R.T.D.	2470

RECEIVED
 STATE CORPORATION COMMISSION

MAY 7 1964

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, Fred S. Barker, do hereby certify that the above is a true and correct copy of the log on the Barnett #1-34, located in the NE SW of Section 34-24S-42W, Hamilton County, Kansas.

EARL F. WAKEFIELD

BY Fred S. Barker

Subscribed and sworn to before me this 5th day of May, 1964.

My commission expires:
 January 25, 1965

Thanda H. Riley
 NOTARY PUBLIC