

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-21,402 -0000

LEASE NAME Henning

WELL NUMBER 2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

330 Ft. from S Section Line

2310 Ft. from E Section Line

LEASE OPERATOR Woodman-Iannitti Oil Company

SEC. 1 TWP. 24S RGE. 17 W

ADDRESS P. O. Box 308, Great Bend, KS 67530

COUNTY Edwards

PHONE# (316) -792-2921 OPERATORS LICENSE NO. 6588

Date Well Completed 10/23/94

Character of Well D&A

Plugging Commenced 10/23/94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10/23/94

The plugging proposal was approved on 10-23-94 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	223'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Mud laden fluid 4400'-1110' 15 sks in rathole
50 sks cement @ 1110' 10 sks in mousehole
50 sks cement @ 250'
10 sks cement @ 40' 10 sks in Water Well

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Woodman-Iannitti Oil Company

STATE OF KANSAS COUNTY OF RUSSELL, ss.


Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) [Signature]

Kyle B. Branum

(Address) Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 25th day of October, 19 94



Glenda R. Tiffin
Glenda R. Tiffin, Notary Public

Commission Expires: 2-6-96

EMPHASIS OIL OPERATIONS
 A Division of N-B Company, Inc.
 P. O. BOX 506
 RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Woodman-Iannitti Oil Company
 P. O. Box 308
 Great Bend, Kansas 67530

CONTRACTOR: Emphasis Oil Operations
 Box 506
 Russell, KS 67665

LEASE: Henning' WELL #2

LOCATION: NW NW NE
 Section 1-24S-17W
 Edwards County, Kansas

LOGGERS TOTAL DEPTH: 4401'

ROTARY TOTAL DEPTH: 4400'

COMMENCED: 10/15/94

CASING: 8-5/8" @ 223' w/150 sks cement

ELEVATION: 2090' K.B.

COMPLETED: 10/23/94

STATUS: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Dakota Sand	300'	Shale & Lime	2135'
Shale	385'	Lime & Shale	2864'
Cedar Hills	590'	Shale & Lime	3198'
Shale	940'	Lime & Shale	3528'
Anhydrite	1090'	Lime	4287'
Shale	1116'	R.T.D.	4400'


STATE OF KANSAS)
) ss
 COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


 Kyle B. Branum

Subscribed and sworn to before me on October 25, 1994.

My commission expires: February 6, 1996.




 Glenda R. Tiffin, Notary Public