

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Edwards SEC. 1 TWP. 24S RGE. 17 W/W  
Location as in quarters or footage from lines:  
SW SW NW


Locate Well  
correctly on above  
Section Platt.

Lease Owner F. G. Holl  
Lease Name Traylor Well No. 1-1  
Office Address 6427 East Kellogg, Wichita, Kansas 67207  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed September 20, 1983  
Application for plugging filed September 20, 1983  
Plugging commenced 4:00 PM September 20, 1983  
Plugging completed 6:00 PM September 20, 1983  
Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bob Carbutton  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4455'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	265'	None

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud plugged through open ended  
drill pipe. 50 sacks 60/40 Pozmix, 2% gel total 4% and  
3% cc at 1110'; 40 sacks at 570'; 40 sacks at 300', bridge,  
1/2 sack hulls, plug and 10 sacks at 40'. 15 sacks in  
rathole with joint of drill pipe. Pulled water well and  
plugged with .5 sacks.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.  
F. A. Wuellner (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY  
(Signature) F. A. Wuellner  
F. A. Wuellner, Secretary  
(Address)  
P. O. Box 129, Sterling, Kansas 67579

SUBSCRIBED AND SWORN TO before me this 21st day of September, 1983



My Commission expires: 4-6-85

Agnes D. Wurst  
Agnes D. Wurst, Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 23 1983 9-23-83

CONSERVATION DIVISION  
Wichita, Kansas

15.047-21116-0000

# STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- TRAYLOR #1-1  
Located: SW SW NW, Section 1-24S-17W, Edwards County, Kansas

OWNER: F. G. Holl  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 14, 1983  
COMPLETED: September 20, 1983

TOTAL DEPTH: 4455'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Soil and Sand	Ran 6 joints 8 5/8", 24# new casing.
90 - 268 Shale	253.04' pipe set at 265' K.B.
268 - 1116 Shale, Sand and Red Bed	Cemented with 210 sacks 60/40 Pozmix with 3% cc. Plug down at 4:00 PM, 9-14-83, by Howco.
1116 - 1137 Anhydrite	
1137 - 1180 Shale	
1180 - 4455 Lime and Shale	Plugged.

Deviation Surveys: 3/4° at 2164'  
1 3/4° at 4390'

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 23 1983  
CONSERVATION DIVISION  
Wichita, Kansas