

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-21282-0000

LEASE NAME Charities

WELL NUMBER 1-1

         Ft. from S Section Line

         Ft. from E Section Line  
1455' FSL & 4-5" FSL NW/4

SEC. 1 TWP. 24S RGE. 17W or (W)

COUNTY Edwards

Date Well Completed         

Plugging Commenced 6-2-87

Plugging Completed 6-5-87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR David W. Clothier

ADDRESS 225 N. Market Suite 300  
Wichita, Kansas 67202

PHONE # (316) 267-9227 OPERATORS LICENSE NO. 3295

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4490'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	311'	none
				4-1/2"	4479'	3145'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.

Plugged off bottom with sand to 4280' and 4 sacks cement. Shot pipe @3541', 3339', 3219', 3145', pulled a total of 77 joints of 4-1/2" casing. Plugged surface with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull, plug and 150 cement, 60/40 pos, 6% gel.  
Plugging Complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 8th day of June, 19 87

Irene Hoover  
STATE CORPORATION COMMISSION  
Notary Public

My Commission Expires:         



JUN 9 1987 6-9-87

CONSERVATION DIVISION Form CP-4  
Wichita, Kansas Revised 07-86

DAVID W. CLOTHIER  
225 North Market-Suite 300  
Wichita, Kansas 67202

CHARITIES LEASE WELL 1-1  
SW NW Sec. 1-24S-17W  
Edwards County, Kansas

## C A S I N G R E C O R D

March 30, 1987

Ran, set and cemented 110 jts. - 4-1/2 "OD 10.5# Brd. R-2&3 SH and  
New casing set @ 4479' -(1' off TD) Run 500 gal. BJ Mud Sweep = Cemented  
w/ 150 sacks 60/40 pozmix cement-2% gel- followed w/ 125 sacks Surefill  
Cement = plug down 10:00 PM

2885' - Range 3 casing SH on bottom of string  
1594' - Range 2 casing New on top of string.

RAN 7-7/8" BIT ON BOTTOM OF CASING INSTEAD OF CASING SHOE.

Shoe joint - 39.41' long - Float @ 4439'

Centralizers: 4438', 4316', 4195', 4033' and 3870'.

Good fluid returns at surface during cementing

Float did hold.

Directions: Belpre - 5 mi. North to Pawnee - EDWARDS CO. Line - West 2  
miles  
South 1/2 mile - East Side.

Supervised by

LeeRoy Cline

LEITH OPERATIONS, INC. 1509 Robin Ridge Circle  
Wichita, Kansas 67230

RECEIVED  
STATE CORPORATION COMMISSION

JUN - 1 1987

CONSERVATION DIVISION  
Wichita, Kansas