



15-047-00062-0000

D. R. Nauck Oil Company, Inc.  
& Sunray Mid-Continent Oil Company

Deckert #1

C NE SW Sec. 25-24S-17W  
Edwards County Kansas

Commenced September 7, 1957  
Completed September 26, 1957

Casing Record: 233' 8 5/8" cem. with 225 sacks  
Elevation: GR 2107; DF 2110; KB 2112

Drillers Log

Tops

Shale & sand	35	Heebner	1755-1643	3756-1644
sand	185	Rotonto	3772-1660	3778-1666
shale	233	Douglas	3796-1684	3796-1684
blue shale	360	Brown Lime	3888-1776	3889-1777
red bed	525	Lansing	3897-1785	3898-1786
Kime shells	533	Cherokee sand	4355-2243	4354-2242
red bed & shells	580	Mississippian	4375-2263	4377-2265
sand	665	Kinderhook		4427-2315
red bed & shells	1123	Kinderhook sand	4436-2324	4436-2324
Anhydrite	1145	Viola	4484-2372	4484-2372
red bed & shale & shells	1220	Rotary Total Depth	4540-2428	4539-2427
shale & shells	1850	DST #1 (W)	4356-4381	open one hour; strong blow throughout; recov. 2840 feet gas cut salt water and fine grained sand. BHP 1480# in 20 min; FP 580-1420#
shale & lime	2430	DST #2	straddle pack. 4440-4468	open 1 hr weak blow 5 min; recov. 5' drilling mud; All pressures 0#.
Lime & Pyrite	2485			
Lime & shale	2545			
lime -shale & Pyrite	2650			
shale & lime	3395			
Lime	3465			
Lime & shale	3625			
Lime	3745			
Lime & shale	3888			
lime	3905			
lime & shale	3960			
lime	4070			
lime & shale	4146			
Lime	4185			
lime & shale	4375			
chert	4381			
shale & chert	4490			
Viola	4540	RTD		

PLUGGING  
FILE SEC. 25 T. 24 R. 17W  
BOOK PAGE 49 LINE 2