

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-21,166-0000

LEASE NAME Stapleton Bros #1-25

WELL NUMBER #1-25

SPOT LOCATION SW NE NE

SEC. 25 TWP. 24 RGE. 17 (W)

COUNTY Edwards

Date Well Completed 4-7-84

Plugging Commenced 11:15 PM  
4-6-84

Plugging Completed 12:05 AM  
4-7-84

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F. G. Holl

ADDRESS 6427 East Kellogg  
Wichita, Kansas 67207

PHONE # ( ) OPERATORS LICENSE NO. \_\_\_\_\_

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? No. 1

Is ACO-1 filed? \_\_\_\_\_ if not, is well log attached? Yes

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4526'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	266'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud. Plugged through open ended drill pipe - 50 sacks at 1140'; 70 sacks at 510'; Bridge, 1/2 sack hulls, plug and 10 sacks at 40'. 15 sacks in rathole, pulled water well and plugged with 5 sacks. Used 60/40 Poxmic, plug 2% gel (total of 4%) and 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P. O. Box 129, Sterling Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STERLING DRILLING COMPANY

(Signature) F. A. Wuellner

(Address) F. A. Wuellner, Secretary  
P. O. Box 129

Sterling, Kansas 67579

SUBSCRIBED AND SWORN TO before me this 9th day of April, 1984.

Agnes D. Wurst  
Agnes D. Wurst, Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

APR 13 1984

CONSERVATION DIVISION  
Wichita, Kansas

My Commission expires:

4-6-85



## STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - STAPLETON BROS #1-25

Located: SW NE NE, Section 25-24S-17W, Edwards County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 1, 1984

COMPLETED: April 7, 1984

TOTAL DEPTH: 4526'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Soil and Sand	Ran 6 joints new 8 5/8", 23# casing.
90 - 268 Clay and Shale	253.19' pipe set at 266' K.B. Cemented
268 - 900 Shale and Sand	with 210 sacks 60/40 Pozmix plus 3% cc.
900 - 1128 Shales - Red Beds	Plug down 12:00 PM, 4-1-84, by Howco.
1128 - 1140 Anhydrite	
1140 - 2000 Shales	
2000 - 4526 Lime and Shale	Plugged.

Deviation Surveys: 3/4° at 2227'  
1 1/2° at 4408'

RECEIVED  
STATE CORPORATION COMMISSION

APR 13 1984

CONSERVATION DIVISION  
Wichita, Kansas