

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-21,336-0000

LEASE NAME Stapleton C

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-25

1650 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 25 TWP. 24 RGE. 17 (E) or (W)

COUNTY Edwards

Date Well Completed 4-20-89

Plugging Commenced 1:30 AM
4-20-89

Plugging Completed 2:30 AM
4-20-89

LEASE OPERATOR F. G. Holl Company

ADDRESS PO Box 780167, Wichita, Kansas 67278-0167

PHONE#(316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on April 19, 1989 (date)

by Steve Pfifer (KCC District Agent's Name).

Is ACO-1 filed? no If not, Is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4450

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	306'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Filled hole with heavy mud. 50 sacks 40x60 Pozmix W/6% gel at 1337'; 40 sacks at 570';
5 sacks at 330'; 10 sacks 40' to surface; 15 sacks in rathole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address PO Box 129, Sterling, Kansas 67579

STATE OF Kansas COUNTY OF Rice, ss.

above-described well was plugged by me, Richard L. Mead, (Employee of Operator) or (Operator) of
Sterling Drilling Company
I, the undersigned, do hereby sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

RECEIVED
APR 21 1989
CONSERVATION DIVISION
Wichita, Kansas

(Signature) Richard L. Mead

(Address) PO Box 129, Sterling, KS 67579

SUBSCRIBED AND SWORN TO before me this 20 day of April, 19 89

Richard L. Mead
F. A. Wuellner Notary Public

My Commission Expires: _____



15-047-21336-0000

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- Stapleton C 1-25
Located SE NE SE, Section 25-25S-17W, Edwards County, Kansas

OWNER: F. G. Holl Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 13, 1989
COMPLETED: April 20, 1989

TOTAL DEPTH: 4550'

LOG

0 - 60	Surface Soil & Sand
60 - 309	Red Bed & Shale
309 - 1121	Shale & Red Beds
1121 - 1133	Anhydrite
1133 - 4550	Lime & Shale

CASING RECORD

Ran 7 joints of 8 5/8" casing 293.55'
set @ 306' KB, cemented with 225 sacks
40 x 60 Pozmix with 2% Gel. & 3% cc.
Plug down on 4-13-89 by B.J. Titan.
Good returns to surface. 11:30 AM

Dry and abandoned. Plugged as follows:
Filled hole with heavy mud and 50 sacks
40 x 60 Pozmix with 6% Gel at 1337';
40 sack at 570'; 50 sacks at 330'; 10
sacks 40' to surface; 15 sacks in rathole.
Job completed at 2:30 A.M. 4-20-89 by
B.J. Titan. State Plugger - Steve Pfifer,
Sterling Drilling witness, Vaughn
Thompson, tool pusher.

Deviation Survey: 3/4° at 4418'

RECEIVED
STATE CORPORATION COMMISSION
STATE CORPORATION

APR 21 1989

CONSERVATION DIVISION
Wichita, Kansas