

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-22,586-0000

LEASE NAME Bookstore

WELL NUMBER 2-1

#1  
TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2970 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 1 TWP. 24 RGE. 14 ~~XXX~~ or (W)

COUNTY Stafford

Date Well Completed 5-3-89

Plugging Commenced 5-3-89

Plugging Completed 5-3-89

LEASE OPERATOR JFW, Inc.

ADDRESS RR 1 Box 26 Plevna, KS 67568

PHONE# (316) 286-5318 OPERATORS LICENSE NO. 9324

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-2-89 Duane Ranken (date)

by Duane Ranken (KCC District Agent's Name).

Is ACO-1 filed? operator if not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4230'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS 5-8-89 CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	<u>8 1989</u>					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Bottom Plug: @4110' w/30 sacks cement thru drill pipe  
Next Plug: @850' w/50 " " " " "  
Next Plug: @450' w/50 " " " " "  
Top Plug: @40' w/10 sacks cement 15 sacks in Rat Hole  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: JFW, Inc

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (Employee of Operator) or ~~(Operator)~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson

(Address) P.O. Box 823 Great Bend, KS 67530



SUBSCRIBED AND SWORN TO before me this 5th day of May, 1989

Dorothy M Hague  
Notary Public

My Commission Expires: 5-5-90

DRILLER'S WELL LOG

DATE COMMENCED: April 25, 1989  
DATE COMPLETED: May 3, 1989

JFW, Inc.  
BOOKSTORE #2-1  
SW SW NW  
Sec. 1, T24S, R14W  
Stafford County, Ks.

- 0 - 419' Surface Soil, Sand
- 419 - 842' Red Bed
- 842 - 855' Anhydrite
- 855 - 1660' Red Bed, Shale, Lime streaks
- 1660 - 1985' Shale & Lime
- 1985 - 3448' Lime & Shale
- 3448 - 3486' Shale & Lime
- 3486 - 3584' Shale
- 3584 - 3608' Lime & Shale
- 3608 - 3856' Lime
- 3856 - 3973' Shale, Lime, Chert, Sand
- 3973 - 4003' Chert and Lime
- 4003 - 4115' Chert
- 4115 - 4160' Sand & Shale
- 4160 - 4230' Dolomite
- 4230' RTD

ELEVATION: 1945 K.B.

Surface Pipe: Set new 8-5/8"  
20# pipe @ 419' w/200 sacks  
60/40 pozmix 2% gel 3% cc.

RECEIVED  
STATE CONSERVATION COMMISSION  
MAY 6 1989  
CONSERVATION DIVISION  
Wichita, Kansas

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

*Leonard Williamson*

Subscribed and sworn to before me this 5<sup>th</sup> day of May 1989.

*Dorothy M. Hague*  
Notary Public

