

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-21,167-0000

LEASE NAME Grizzelle

WELL NUMBER 2-11

SPOT LOCATION SW SE NW

SEC. 11 TWP. 24 SRGE. 17

COUNTY Edwards

Date Well Completed 4-14-84

Plugging Commenced 5:00 AM,

4-14-84

Plugging Completed 6:30 AM,

4-14-84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F. G. Holl

ADDRESS 6427 East Kellogg  
Wichita, Kansas 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #1

Is ACO-1 filed?            If not, is well log attached? Yes

Producing formation            Depth to top            bottom            T.D. 4540'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	263'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from    feet to    feet each set.

Filled hole with heavy mud, 50 sacks at 1140'; 50 sacks at 570'; 40 sacks at 300'; 10 sacks, 1/2 sack hulls and plug for bridge at 40'. 15 sacks in rathole; 5 sacks in water well. Used 60/40 Pozmix, 2% gel and 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
F. A. Wuellner, Secretary-Treasurer  
(Address) P. O. Box 129

SUBSCRIBED AND SWORN TO before me this 16th day of April, 1984.

[Signature]  
Agnes D. Wurst, Notary Public

My Commission expires: 4-6-85

RECEIVED  
STATE CORPORATION COMMISSION  
APR 18 1984  
CONSERVATION DIVISION  
Wichita, Kansas

# STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - GRIZZELLE #2-11  
Located: SW SE NW, Section 11-24S-17W, Edwards County, Kansas

OWNER: F. G. Holl  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 8, 1984  
COMPLETED: April 14, 1984

TOTAL DEPTH: 4540'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Soil and Sand	Ran 6 joints new 8 5/8", 23# casing. 251.16' pipe set at 263' K.B. Cemented with 210 sacks 60/40 Pozmix with 3% cc. Plug down at 12:15 PM, 4-8-84, by Howco.
90 - 266 Shale	
266 - 861 Shale and Sand	
861 - 1130 Red Beds and Shale	
1130 - 1150 Anhydrite	
1150 - 1185 Shales	
1185 - 4540 Lime and Shale	Plugged.

Deviation Surveys: 1/2° at 2183'  
1 3/4° at 4406'

RECEIVED  
STATE CORPORATION COMMISSION

APR 18 1984

CONSERVATION DIVISION  
Wichita, Kansas