

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-21,354-0000

LEASE NAME Enlow-Miller

WELL NUMBER 8-11

1980 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 11 TWP. 24SRGE. 17W. 24N. (W)

COUNTY Edwards

Date Well Completed April 30, 1990
5:30 PM

Plugging Commenced 4-30-90

7:00 PM

Plugging Completed 4-30-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F. G. Holl Company

ADDRESS P. O. Box 780167
Wichita, Kansas 67278-0167

PHONE#(316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well Dry Hole

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-30-90 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached? Yes

Producing Formation Depth to Top Bottom T.D. 4596'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	318'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Fill hole with heavy mud. Plugged with Heavy mud to 1150' with 50 sacks at 1150';
50 sacks at 600'; 40 sacks at 360'; 15 sacks at 60'; 15 sacks in rathole. Used
60/40 Pozmix with 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P. O. Box 129
Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) F. A. Wuellner
F. A. Wuellner, Secretary

(Address) P. O. Box 129, Sterling, KS 67579

SUBSCRIBED AND SWORN TO before me this 1st day of May, 1990



Agnes D. Wurst, Notary Public

My Commission Expires: 4-26-93

15-047-21354-0000

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - ENLOW-MILLER #8-11

Located: C NE SW, Section 11-24S-17W, Edwards County, Kansas

OWNER: F. G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 24, 1990

COMPLETED: April 30, 1990

TOTAL DEPTH: 4596'

LOG

CASING RECORD

<p>0 - 90 Surface Soil and Sand</p> <p>90 - 1000 Red Beds and Shale</p> <p>1000 - 4596 Lime and Shale</p>	<p>Ran 7 joints 8 5/8" casing. 305.44' pipe set at 318' K.B. Cemented with 225 sacks 60/40 Pozmix, 2% gel and 3% cc. Plug down at 1:30 PM, 4-24-90, by B. J. Titan.</p> <p>Plugged.</p>
---	---

Deviation Surveys: 3/4° at 4423'
1 1/2° at 4596'