

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15.047-20611-0000

LEASE NAME Brensing

WELL NUMBER 2-12

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 12 TWP. 24S RGE. 17 (E) or (W)

COUNTY Edwards

Date Well Completed         

Plugging Commenced 8-3-90

Plugging Completed 8-9-90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F.G. Holl

ADDRESS Box 158 Belpre, KS. 67519

PHONE (316) 995-3171 OPERATORS LICENSE NO. 5056

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by          (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	276'	none
				4 1/2"	4398'	2423'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.

Sanded bottom to 4260' dumped 4 sacks cement. Shot pipe  
@2631', 2423'. Mixed 300# hulls, 20 sacks gel, 50 sacks  
cement, 10 sacks gel, 100# hulls, 100 sacks cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,  
statements, and matters herein contained and the log of the above-described well as filed that  
the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*

(Address) P.O. Box 347 Chase, KS. 67524

RECEIVED  
STATE CORPORATION COMMISSION

**AUG 22 1990** SUBSCRIBED AND SWORN TO before me this 20 day of August, 19 90

CONSERVATION DIVISION  
Wichita, Kansas

My Commission Expires:         



*Irene Herzberg*  
Notary Public

15-047-25611-0000

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG - - - - - BRENSING "B" 2-12  
Located: 440' PSL, 50' FEL, NW/4, Section 12-24S-17W,  
Edwards County, Kansas

OWNER: F. G. Holl  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: December 27, 1979  
COMPLETED: January 2, 1980

TOTAL DEPTH: 4400'

LOG

CASING RECORD

0 - 35	Surface Soil and Sand	Ran 6 joints used 8 5/8", 24# casing, 264.76' set at 276.76 K.B. with 225 sacks 60/40 Pozmix with 3% cc. Plug down at 3:00 PM, 12-27-79, by Howco.
35 - 279	Shale	
279 - 1105	Shale, Sand and Red Bed	
1105 - 1130	Anhydrite	
1130 - 1175	Shale and Shells	
1175 - 2105	Shale and Lime Strs.	
2105 - 4240	Shale and Lime	
4240 - 4298	Lime and Shale - Chert	
4298 - 4400	Chert, Shale, Sand	Ran 112 joints new 10.50#, 4 1/2" new casing, 4380.01' set at 4396' K.B. with 175 sacks Cement, 50' rotating scratchers - cemented with 175 sacks 50/50 Pozmix with 2% gel, 18% salt, 5# gilsonite per sack, 3/4 of 1% CFR-2. Plug down at 8:15 AM, 1-2-80.

Deviation Surveys: 1 3/4° at 2145'  
2° at 4298'

RECEIVED  
STATE CORPORATION COMMISSION

APR 23 1980

CONSERVATION DIVISION