

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-20477-0000

LEASE NAME Brensing

WELL NUMBER B 1-12

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 12 TWP. 24 SRGE. 17 (E) or (W)

COUNTY Edwards

Date Well Completed

Plugging Commenced 8-2-90

Plugging Completed 8-9-90

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F.G.Holl Company

ADDRESS P.O. Box 158 Belpre, KS. 67519

PHONE#(316) 995-3171 OPERATORS LICENSE NO. 5056'

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 4406'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	250'	none
				4 1/2"	4407'	1175'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom to 4225' dumped 4 sacks cement. Plugged with
3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, 150 sacks 60/40
6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524 8-15-90

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F. G. Holl Company WFS

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 14 day of August, 19 90

Irene Herzberg
Notary Public

My Commission Expires:



STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - BRENSING "B" #1-12
Located: SW SW NW, Section 12-24S-17W, Edwards
County, Kansas

OWNER: F. G. Holl, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 24, 1979
COMPLETED: January 31, 1979

TOTAL DEPTH: 4410'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 72 Clay and Sand	Ran 6 joints new 24#, 8 5/8" casing, 238.40' set at 250' K.B. with 225 sacks 60/40 Pozmix with 3% cc. Plug down at 9:30 PM, 1-24-79, by Howco.
72 - 253 Sand and Shale	
253 - 400 Shale	
400 - 1114 Red Beds	
1114 - 1132 Anhydrite	
1132 - 1465 Shale	
1465 - 1988 Shale and Lime Strs.	
1988 - 2160 Shale and Shells	
2160 - 2389 Shale	
2389 - 4300 Lime and Shale	
4300 - 43700 Shale, Lime and Chert	
4370 - 4410 Lime and Shale	Ran 139 joints new 10.5#, 4 1/2" casing, 4396.70' set at 4407' K.B. with 50 sacks Howco Light and 1000sacks 50/50 Pozmix with 18% salt and 5# gilsonite and 1/8# tuffiber and 1/8# flocele and 3/4% CER-2 per sack. Plug down at 11:00 PM, 1-31-79, by Howco. 20 bbl. salt flush and 250 gal. mud flush ahead of cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 23 1990

CONSERVATION DIVISION
Wichita, Kansas