

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg,  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Edwards SEC. 12 TWP. 24S RGE. 17 me E/W  
Location as in quarters or footage from lines:  
SW NW NW


Locate Well  
correctly on above  
Section Platt.

Lease Owner F. G. Holl  
Lease Name Brensing "B" Well No. 6-12  
Office Address 6427 East Kellogg, Wichita, Kansas 67207  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed December 22, 1983  
Application for plugging filed December 22, 1983  
Plugging commenced 10:45 AM, December 22, 1983  
Plugging completed 12:00 Noon December 22, 1983  
Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthie  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4460'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	265'	None

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud.  
Plugged with 50 sacks at 1140'; 70 sacks at 520';  
10 sacks at 40' with 1/2 sack hulls, Howco plug  
and solid bridge; 15 sacks in rathole; 10 sacks in  
mouse hole; 5 sacks in water well. Used 160 sacks  
60/40 Pozmix, 2% gel and 3% cc.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF RICE COUNTY OF KANSAS, ss.

Richard L. Mead (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY  
(Signature) Richard L. Mead  
Richard L. Mead  
(Address)  
P. O. Box 129, Sterling, Ks 67579



SUBSCRIBED AND SWORN TO before me this 23rd day of December, 19 83.

Agnes D. Wurst  
Notary Public.

My Commission expires: 4-6-83

RECEIVED  
STATE CORPORATION COMMISSION

DEC 28 1983 12-28-83

15-047.21144-0000

# STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - BRENSING "B" 6-12  
Located: SW NW NW, Section 12-24S-17W, Edwards County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: December 15, 1983

COMPLETED: December 22, 1983

TOTAL DEPTH: 4460'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Soil and Sand	Ran 6 joints 8 5/8", 24# casing. 252.14' pipe set at 265' K.B.
90 - 267 Shale	Cemented with 210 sacks 60/40 Pozmix, plus 3% cc. Plug down at 3:30 PM, 12-15-83, by Howco.
267 - 1135 Red Bed, Shale, Lime	
1135 - 1995 Shale	
1995 - 4460 Lime and Shale	Plugged.

Deviation Surveys: 1° at 2154'  
2° at 4347'

RECEIVED  
STATE CORPORATION COMMISSION

DEC 28 1983

CONSERVATION DIVISION  
Wichita, Kansas