

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-075-20611-0000

LEASE NAME Schwieterman

WELL NUMBER 1

4030 Ft. from S Section Line

3620 Ft. from E Section Line

SEC. 17 TWP. 25 SRGE. 40 (E) or (W)

COUNTY Hamilton

Date Well Completed N/A

Plugging Commenced 1:06am/10-6-

Plugging Completed 2:58am/10-6-

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Horseshoe Operating, Inc.

ADDRESS 500 W. Texas, Suite 1190, Midland, TX 79701

PHONE# (915) 683-1448 OPERATORS LICENSE NO. 4894

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-5-96 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? no If not, Is well log attached? Yes

Producing Formation Winfield Depth to Top 2312 Bottom 2348 T.D. 2366

Show depth and thickness of all water, oil, and gas formations.

11-24-96

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

Formation	Content	From 267	To 0	Size 8 5/8"	Put in 267	Pulled out 0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pumped down drill pipe cement, 60/40 POZ-6% gel-1/4# floccul 50 sx from 1850' to 1750', 2nd plug 80 sx from 650' to 450', 3rd plug 40sx from 280' to 180', 4th plug 10sx from 40' to surface. 15sx rathole and 10sx mouse hole.
Used drilling mud to displace cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Dowell License No. _____

Address P. O. Box 4378, Houston, TX

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Horseshoe Operating, inc.

STATE OF Kansas COUNTY OF Seward, ss.

Terry Maxwell, Agent

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry W Maxwell

(Address) P. O. Box 800, Liberal, KS 67905

SUBSCRIBED AND SWORN TO before me this 18 day of November, 1996

Gonda D Maxwell
Notary Public

My Commission Expires: 12-13-96

