


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15. 167. 00026. 00. 00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

Russell County, Sec. 15 Twp. 14 Rge. 13 (E) W. (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE NW
Lease Owner Duke & Wood Drilling Company, Inc.
Lease Name Dumlar Well No. 1
Office Address Box 194, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 5, 1952
Application for plugging filed May 5, 1952
Application for plugging approved May 5, 1952
Plugging commenced May 6, 1952
Plugging completed May 6, 1952
Reason for abandonment of well or producing formation Dry
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2432 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 247' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud, set bottom at 240', dumped 20 sacks wet cement thru drill pipe on bottom plug, Filled hole with heavy mud to 40', set top plug, dumped 10 sacks wet cement on top plug. Filled to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAY 9 1952
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Duke & Wood Drilling Company, Inc.
Address Box 194, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Cecil M. Olson (employee of owner) ~~of the above-described well~~
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Cecil M. Olson
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of May, 1952

Dean L. Cooley
Notary Public.

My commission expires April 29, 1953.

PLUGGING
FILE SEC 15 T 14 R 13W
BOOK PAGE 14 LINE 18

WELL LOG
Dumler #1
SE SE NW Section 15-14-13
Russell County, Kansas

Started: April 29, 1952
Completed: May 6, 1952

Elevation 1843 D. F.
Anhydrite 784 (-1061)
Tarkio 2377 (-532)

| | |
|-----------|------------------------------|
| 0-80 | Surface clay and post rock |
| 80-247 | Shale, clay and sand streaks |
| 247-460 | Shale, sand and iron |
| 460-784 | Shale, clay and red bed |
| 784-821 | Anhydrite |
| 821-1185 | Shale and shells |
| 1185-1600 | Salt, shale and broken lime |
| 1600-1885 | Lime |
| 1885-2055 | Lime |
| 2055-2255 | Lime and shale |
| 2255-2377 | Lime and shale |
| 2377-2432 | Tarkio sand and shale |
| 2432 | TOTAL DEPTH |

A F F I D A V I T

STATE OF Kansas, COUNTY OF Barton SS


I, Lynn O. Duke of the DUKE & WOOD DRILLING COMPANY, INC.
being first duly sworn on oath, state; That I have knowledge of the facts,
statements and matters herein contained and that the same are true and
correct.

[Signature]
Vice-President

Subscribed and sworn to before me this 8th day of May 1952.

[Signature]
Notary Public

My commission expires: April 29, 1953.



RECEIVED
WATER RESOURCES
DIVISION COMMISSION
MAY -9 1952
CONSERVATION DIVISION
Wichita, Kansas