


STATE OF KANSAS
STATE CORPORATION COMMISSION

15.167.00482.00.00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Russell County. Sec. 21 Twp. 13 Rge. 15w (Ex) (W)
Location as "NE/CNW/SW" or footage from lines SW NE SE
Lease Owner Womer Oil Company
Lease Name Mills Estate Well No. 1
Office Address 434 Ohio, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 19, 19 60
Application for plugging filed March 19, 19 60
Application for plugging approved March 19, 19 60
Plugging commenced March 19, 19 60
Plugging completed March 19, 19 60
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes.

Name of Conservation Agent who supervised plugging of this well Donald Truan, 634 Sunset, Russell, Kansas.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3371 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 200', 1/4 sax hulls, Halliburton plug, 25 sax cement through drill pipe. Mud to 35', 1/2 sax hulls, Halliburton plug, 10 sax cement, cementing to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1960

3-23-60

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Bergman Drilling, Inc.
Address 425 Union Center, Wichita, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Harold Bergman (employee or owner of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Bergman
Harold Bergman, BERGMAN DRILLING, INC.

SUBSCRIBED AND SWORN TO before me this 22nd day of March, 19 60
425 Union Center (Address) Wichita 2, Kansas

My commission expires June 30, 1963.
Cecile L. Lawson Notary Public.



15.167.00482.00.00

WELL LOG

#1 Mills Estate, SW NE SE, Section 21, T13w, R15w, Russell County, Kansas.

Date Started: March 8, 1960

Date Completed: March 19, 1960

0- 90	Post Rock
90- 207	Sand Shells-Shale
207- 400	Shale - Red Bed
400- 520	Shale
520- 610	Red Bed Sand
610- 720	Shale sand, Red Bed
720- 880	Shale Shells
880- 930	Shale Shells
930- 970	Anhydrite
970-1000	Shale, Red Bed
1000-1170	Shale, Red Bed
1170-1595	Shale, Salt Shale
1595-1725	Shale Shells
1725-1805	Shale Shells
1805-1915	Lime & Shale
1915-2005	Shale & Lime Shells
2005-2055	Shale Lime
2055-2175	Lime & Shale
2175-2315	Lime Shale
2315-2400	Shale - Shells
2400-2440	Shale & Shells
2440-2680	Shale, Shells & Streaks of Lime
2680-2805	Lime & Shale, Topeka
2805-2860	Shale & Lime
2860-2925	Lime & Shale
2925-2980	Lime & Shale
2980-3037	Lime Shale
3037-3095	Lime
3095-3114	Lime, Lansing
3114-3120	Lime
3120-3160	Lime
3160-3205	Lime
3205-3245	Lime
3245-3269	Lime
3269-3325	Lime
3325-3371	Conglomerate Shale Lime
3371	Total Depth.

ELEVATION: 1892 K.B.

GEOLOGICAL TOPS:

Anhydrite	930
Howard	2740
Topeka	2785
Heebner	3012
Toronto	3028
Douglas	3045
Lansing	3059
Conglomerate	3322
Arbuckle	3351
Total Depth	3371

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1960
CONSERVATION DIVISION
Wichita, Kansas

A F F I D A V I T

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I, do swear that the statements and matter herein contained are true to the best of my knowledge.

BERGMAN DRILLING, INC.

Harold Bergman
Harold Bergman

Subscribed and sworn to before me this 22nd day of March, 1960.

My commission expires: June 30, 1963.

Cecile L. Lawson
Cecile L. Lawson, Notary Public