


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Russell County. Sec. 19 Twp. 13 Rge. 15 (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner R. P. Nixon
Lease Name Polcyn Well No. 1
Office Address 754 East Wichita Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed May 30 1958
Application for plugging filed June 2 1958
Application for plugging approved _____ 19____
Plugging commenced May 30 1958
Plugging completed May 30 1958
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3400 Feet
Show depth and thickness of all water, oil and gas formations. none

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug set at 200'. Cemented with 1/4 sack of hulls and 25 sx cement. Mud up to 40'. Set plug at 40'. Cemented with 1/4 sack of hulls and 14 sacks of cement to bottom of cellar.

6-14-58

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Triangle Drilling, Inc.
Address Box 287 Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
R. P. Nixon ~~Employee of owner~~ (or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. P. Nixon
754 East Wichita Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of June, 1958

My commission expires 12-9-59

Joan Hanes
Notary Public.

PLUGGING
FILE SEC 19 T. 13 R. 15W
BOOK PAGE 104 LINE 35

WELL LOG

COMPANY	R. P. Nixon
CONTRACTOR	Triangle Drilling, Inc.
FARM	#1 Polcyn
LOCATION	NW NW SE of Section 19-13-15W Russell County, Kansas
ELEVATION	1936 KB
SURFACE PIPE	8 5/8" cemented @ 205* w/135 sacks common
PRODUCTION	D & A
COMMENCED	May 19, 1958
COMPLETED	May 30, 1958

FORMATION

DEPTH TO BOTTOM
OF FORMATION

Surface clay	8
Sandstone	20
Shale and sandstone	60
Shale and shells	340
Sandstone	400
Shale and sandstone	440
Shale and shells	560
Sandstone	655
Shale and sandstone	695
Red bed	1001
Anhydrite	1038
Shale and shells	1595
Limestone and shale	1675
Broken limestone	1980
Limestone	2105
Sandy limestone	2120
Limestone, shale and sandstone	2175
Limestone and shale	2849
Limestone	3389
Dolomite	3400

FORMATION TOPS

Anhydrite	1001 (✓ 935)
Topeka	2849 (- 913)
Heebner	3074 (-1138)
Toronto	3093 (-1157)
Lansing	3122 (-1186)
Arbuckle	3389 (-1453)
RTD	3400 (-1464)

RECEIVED
STATE CORPORATION

JUN 7 1958

A F F I D A V I T

STATE OF KANSAS, COUNTY OF BARTON, SS.

CONSERVATION DIVISION
Wichita, Kansas

I, Donald D. Vaughan, of the TRIANGLE DRILLING, INC., being first duly sworn on oath, state; That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Donald D. Vaughan
Donald D. Vaughan

Subscribed and sworn to before me this 5th day of June, 1958.

PLUGGING
FILE SEC. 19 T. 13 R. 15W
BOOK PAGE 104 LI 35

Dean E. Cooley
Notary Public

My commission expires: April 29, 1961.