

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Kingman County, Sec. 35 Twp. 30 Rge. 8 (EX) (W)

Location as "NE/CNW/SW" or footage from lines C NW SE

Lease Owner Mull Drilling Company, Inc.

Lease Name Washburn Well No. 1

Office Address 6405 E. Kellogg, Wichita 18, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed 4/7 19 56

Application for plugging filed 4/7 19 56

Application for plugging approved 4/7 19 56

Plugging commenced 4/7 19 56

Plugging completed 4/7 19 56

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well 4504 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	160'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole was filled with heavy rotary mud to 160'. Plug set at 160' 15 sacks of cement on top of plug and filled hole with heavy mud to 30'. Set plug at 30', 10 sacks of cement on top of plug. 8 5/8" pipe cut off three feet below the surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mull Drilling Company, Inc.

Address 6405 E. Kellogg, Wichita 18, Kansas


STATE OF Kansas, COUNTY OF Sedgwick, ss.

J. A. Mull, Jr. President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. MULL, JR. 6405 E. Kellogg, Wichita 18, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 10th day of April, 19 56

My commission expires January 28, 1957



Ethel Zimmerman Notary Public.

PLUGGING
SEC 35 T 30 R 8W
BOOK PAGE 52 LINE 5

4-17-56
CONSERVATION DIVISION
Wichita, Kansas

ROTARY DRILLERS LOG

COMPANY : Mull Drilling Company, Inc. ROTARY DRILLING COMMENCED: 3-24-56
Wichita, Kansas

CONTRACTOR : Mull Drilling Company, Inc. ROTARY DRILLING COMPLETED: 4-7-56
Wichita, Kansas

CASING RECORD : Set 160' of 8 5/8" Surf. Csg. LOCATION: WASHBURN #1
cemented with 135 sacks cement C. NW SE of Sec. 35-30-8W
Kingman County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing.)

Clay	20
Sand	120
Red Rock	160
Red Bed & Shale	1190
Shale & Lime	3759
Lime	4247
Lime & Shale	4388
Lime (Mississippi)	4504 R.T.D.

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.

J. A. Mull, Jr.
J. A. MULL, JR., PRESIDENT

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

Subscribed and sworn to before me this 10th day of April, 1956.

Ethel Zimmerman
NOTARY PUBLIC

MY COMMISSION EXPIRES: JANUARY 28, 1957

PLUGGING
SEC 35 T 30 R 8 W
BOOK PAGE 52 LINE 5

PLUGGING DIVISION
Wichita, Kansas