

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kingman SEC. 35 TWP. 30s RGE. 8W E/W
Location as in quarters or footage from lines:
C SE SE

Locate Well
correctly on above
Section Platt.

Lease Owner Robert E. Campbell
Lease Name Alldritt #1 Well No. _____
Office Address Suite 110, 260 N. Rock Rd., Wichita, Ks. 67206
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 6/26/81
Plugging completed 7/1/81
Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie

Producing formation _____ Depth to top _____ bottom _____ T.D. 4417'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	209'	None
				4 1/2"	4416'	3864'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Moved onto location. Ran sand to 4350' and set 4 sacks cement. Pulled 29" stretch.
Shot pipe at 3870' and pulled a total string of 120 joints. Plugged well with 25
sacks gel, 8 sacks hulls and 125 sacks 50/50 pos 4% gel 3% cc. Plugging complete

7-8-81

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have known the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of July, 19 81

My Commission expires:



Joan Kelso
Notary Public.

DRILLER'S LOG

Operator: Robert E. Campbell
 Lease Name: Aldritt #1
 Spot Location: C SE SE
 Sec. 35-30S-8W
 County, State: Kingman County, Kansas


Commenced: 03-07-80
 Completed: 03-14-80

Surface Casing: 5 joints 8 5/8" Used 24 lb. Set @ 209'. 225 sks Common; 3% cc; 2% gel. Cement did circulate.

<u>FORMATION</u>	<u>DEPTH</u>
<u>Sand & Red Bed</u>	<u>0 - 206</u>
<u>Red Bed & Shale</u>	<u>206 - 1355</u>
<u>Shale & Lime</u>	<u>1355 - 3740</u>
<u>Lime</u>	<u>3740 - 3898</u>
<u>Lime & Shale</u>	<u>3898 - 4015</u>
<u>Lime</u>	<u>4015 - 4417</u>
	<u>TD - 4417</u>

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 18 1981
 CONSERVATION DIVISION
 Wichita, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.


EAGLE DRILLING, INC.

 W. C. Amend
 Vice-President

STATE OF KANSAS)
 COUNTY OF SEDGWICK) ss:

Subscribed and sworn to before me this 17th day of March, 1980.

My appointment expires: August 13, 1983

SHARON WINTER
 STATE NOTARY PUBLIC
 SEDGWICK COUNTY, KS.
 My App. Exp. 08-13-83


 Notary Public Sharon Winter