

1052309

TO: STATE CORPORATION COMMISSION

API NUMBER 15-185-23,081-0000
NW SE SEC. 32, T 24 S, R 15 W

4-12

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME SEIBERT WELL # 2-32

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD 149.55

OPERATOR LICENSE # 31021

WELL TOTAL DEPTH 4540 FEET

OPERATOR: CASTELLI EXPLORATION PRODUCTION CSG: SIZE 4 1/2" @ 4423' WITH 185 SX

NAME AND 9500 WESTGATE DR. STE. 101 SURFACE CASING: SIZE 8 5/8" @ 335' WITH 225 SX

ADDRESS OKLAHOMA CITY, OK 73162

ABANDONED OIL WELL GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 8:30 AM DAY: 12 MONTH: 04 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 4222-62, 3928-31, 3826-30

SANDED TO 3770' AND 4 SX CEMENT. PUMP DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 100 SX CEMENT. MAXIMUM PRESSURE 350#. SHUT IN PRESSURE 200 PSI.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 10:00 AM DAY: 12 MONTH: 04 YEAR: 1999

ACTUAL PLUGGING REPORT

SANDED TO 3770' AND 4 SX CEMENT. PUMP DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS RECEIVED 100 SX CEMENT. MAXIMUM PRESSURE 350#. SHUT IN PRESSURE 200 PSI.

4-22-99

APR 22 1999

CONSERVATION DIVISION
Wichita, Kansas

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2700' OF 4 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacey
(TECHNICIAN)

FORM CP-2/3

INVOICED

DATE APR 26 1999

INV. NO. 60879