

To: 1 041238  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

3-19

API NUMBER 15-4/29/62 15-047-10024-0000  
SW SE SW, SEC. 34, T 24 S, R 16 WEX

TECHNICIAN'S PLUGGING REPORT

Operator License / 8061

Operator: Oil Producers, Inc. of Kansas  
Name:  
Address P.O. Box 8647  
Wichita, KS 67208

330 feet from S section line  
3630 feet from E section line

Lease Name Meyer A Well # 1  
County Edwards 148.13

Well Total Depth 4558 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 438

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67526

Company to plug at: Hour: 9:30 a.m. Day: 19 Month: 3 Year: 19 97

Plugging proposal received from Kent Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

logs: 4 1/2" at 4358' w/200 sx cement, CIBP at 4254', Perfs at 4261-66, 4234-47, 3988-87, 3945-48,

1st plug sand back to 3780' and dump 4 sx cement on top of sand through bailer, 3834-36'

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement. 3-21-97

RECEIVED  
KANSAS CORP COM  
1997 MAR 25 3 33 PM '97

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10:15 a.m. Day: 19 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3780' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released

8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 300 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1900' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

I (could) observe this plugging.

INVOICED  
DATE 3-26-97  
INV. NO. 47821  
3-19

Signed Stephen Pfeifer (TECHNICIAN)