

1 030420

P

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 075-20,047-6000

C NE NE, SEC. 18, T 24 S, R 41 W/EX
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5575

Lease Name Federal Well # 1-18

Operator: Mesa Petroleum Co.

County Hamilton 74.69

Name & Address P. O. Box 2009

Well Total Depth 2298 feet

Amarillo, TX 79189

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 372 ✓

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 10:00 am Day: 24 Month: May Year: 19 85

Plugging proposal received from Tommy Rogers

(company name) Sargent's (phone) 316-624-7455

were: 4 1/2" at 2331' PBTD 2295' Perfs at 2287 & 2295'

1st plug pump 1 sx hulls and 25 sx cement to bottom - Pump through 4 1/2" with mud between plugs

2nd plug at 2300' with 50 sx cement

3rd plug at 1500' with 35 sx cement

4th plug at 1050' with 50 sx cement

5th plug at 425' with 50 sx cement
solid bridge Plugging Proposal Received by Steve Durrant

6th plug hulls - plug at 40' -- cement to surface with 10 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:00 am Day: 28 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls and 25 sx cement to bottom, 2nd plug at 2300' with 50 sx cement, 3rd plug at 1500' with 35 sx cement, 4th plug at 1050' with 50

sx cement, 5th plug at 425' with 50 sx cement, 6th & 7th plugs, solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 31 1985 5-31-85

Recovered 2008' of tubing CONSERVATION DIVISION

Recovered 1500' 4 1/2" casing Wichita, Kansas

Remarks: Used common cement by Sargent's

(If additional description is necessary, use BACK of this form.)

(Do not) observe this plugging.

INVOICED

Signed Steve Durrant (TECHNICIAN)

DATE 6-6-85

INV. NO. 8346
5-28