

1 060040

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 093-21,110 - 0000  
*E/2 NE SW*  
~~N/2 NW SE~~, SEC. 10, T 24 S, R 37 W/E

1980 feet from S section line

3150 - 2130 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4328

Lease Name Eatinger Well # 5-10

Operator: Global Natural Resources Corp.

County Kearny

Name & Address P.O. Box 4682

Well Total Depth 5100 feet

Houston, TX 77210

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1600

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor BEREDCO Inc. License Number 5147

Address 401 E. Douglas, #402, Wichita, KS 67202

Company to plug at: Hour: 9:15 p.m. Day: 3 Month: 10 Year: 19 90

Plugging proposal received from Ken

(company name) BEREDCO Inc. (phone) 316-265-3856

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1590-1630'

1st plug at 3130' with 100 sx cement, 2nd plug at 1640' with 50 sx cement,

3rd plug at 1020' with 50 sx cement, 4th plug at 510' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Case Morris  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 1:45 a.m. Day: 4 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 3130' with 100 sx cement,

2nd plug at 1640' with 50 sx cement,

3rd plug at 1020' with 50 sx cement,

4th plug at 510' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Halliburton.

(If additional description is necessary, use BACK of this form for \_\_\_\_\_)  
Wichita, Kansas

I (XXX / did not) observe this plugging.

Signed [Signature]  
(TECHNICIAN)

11-15-90

RECEIVED

STATE CORPORATION COMMISSION

NOV 15 1990

[Handwritten initials]

EFFECTIVE DATE: 9-18-90

2nd Correction

FORM MUST BE TYPED  
FORM C-1 4/90

AMENDED

State of Kansas

AMENDED

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C. five (5) days prior to commencing well

Expected Spud Date: 9 month, 20 day, 90 year

E/2 NE SW Sec 10 Twp 24 S, Rg 37 West

OPERATOR: License # 4328  
Name: Global Natural Resources Corp.  
Address: P.O. Box 4682  
City/State/Zip: Houston, Texas 77210  
Contact Person: Malynda Mosley  
Phone: (713) 880-5464

CONTRACTOR: License # 5147  
Name: Beredco, Inc.

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Inj ... Infield XX Mud Rotary  
... Gas ... Storage X Pool Ext. ... Air Rotary  
... OWD ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes

If OWO: old well information as follows:  
Operator: ...  
Well Name: ...  
Comp. Date: ... Old Total Depth

Directional, Deviated or Horizontal wellbore? ... yes X no  
If yes, total depth location:

1980 feet from South line of Section  
3150 feet from East line of Section  
(Note: Locate well on Section Plat on Reverse Side)

County: Kearny  
Lease Name: Eatinger Well #: 5-10  
Field Name: Hartland  
Is this a Prorated Field? ... yes X no  
Target Formation(s): St. Louis  
Nearest lease or unit boundary: 1980  
Ground Surface Elevation: 3252.6 feet MSL  
Domestic well within 330 feet: ... yes X no  
Municipal well within one mile: ... yes X no  
Depth to bottom of fresh water: 270  
Depth to bottom of usable water: 700  
Surface Pipe by Alternate: X 1 ... 2  
Length of Surface Pipe Planned to be set: 1640  
Length of Conductor pipe required: None  
Projected Total Depth: 5100  
Formation at Total Depth: St. Louis  
Water Source for Drilling Operations:  
X well ... farm pond ... other  
DWR Permit #: Applied for  
Will Cores Be Taken? ... yes X no  
If yes, proposed zone:

WAS: 2970 FEL

AFFIDAVIT

15' 3150 FEL

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

It is agreed that the following minimum requirements will be met:

- 1. The appropriate district office shall be notified before setting surface pipe;
- 2. The minimum amount of surface pipe as specified above shall be set by circulating cement to the top; in all cases surface pipe shall be set through all unconsolidated materials plus a minimum of 20 feet into the underlying formation;
- 3. If the well is dry, a plugging proposal shall be submitted to the district office. An agreement between the operator and the district office on plug length and placement is necessary prior to plugging;
- 4. The appropriate district office will be notified before well is either plugged or production casing is cemented in;
- 5. If an Alternate II completion, production pipe shall be cemented from below any usable water to surface within 120 days of spud date. In all cases, notify district office prior to any cementing.

I hereby certify that the statements made herein are true and to the best of my knowledge and belief.

Date: 11/5/90 Signature of Operator or Agent: Malynda Mosley Title: Regulatory Analyst

FOR KCC USE:  
API # 15-093-21,116-0000  
Conductor pipe required: None feet  
Minimum surface pipe required: 220 feet per Alt. D  
Approved by: Malynda Mosley 11-13-90; sig 9-13-90  
EFFECTIVE DATE: 9-18-90  
This authorization expires: 3-13-91  
(This authorization void if drilling not started within 6 months of effective date.)  
Spud date: Agent:

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 6 1990  
CONSERVATION DIVISION  
Wichita, Kansas

REMEMBER TO:

- File Drill Pit Application (form CDP-1) with Intent to Drill;
- File Completion Form ACO-1 within 120 days of spud date;
- File acreage attribution plat according to field proration orders;
- Notify appropriate district office 48 hours prior to workover or re-entry;
- Submit plugging report (CP-4) after plugging is completed;
- Obtain written approval before disposing or injecting salt water.

NOV 15 1990

CONSERVATION DIVISION  
Wichita, Kansas

10 24 3745