

1-120409

4-11  
API NUMBER 15- 185-20,967-0000 R: 122

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE NW NE, SEC. 30, T 24 S, R 14 W/E  
4290 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4419

Lease Name Dykes Well # 1

Operator: Bear Petroleum  
Name & Address: Box 438  
Haysville, KS 67060

County Stafford 142.55  
Well Total Depth 4386 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 425

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11:30 a.m. Day: 11 Month: 4 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 5 1/2" at 4384' w/150 sx cement. Open hole

1st plug sand back to 4335' and dump 5 sx cement on top of sand through bailer,

2nd plug pump in 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls and 125 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:30 p.m. Day: 11 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4335' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls and 125 sx cement.

Pumping pressure 0-600 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 1829' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-24-90

INV. NO. 27929

observe this plugging.

CONSERVATION DIVISION  
Wichita, Kansas

4-18-90 Signed Duane Rankin (TECHNICIAN)