

1 050700

API NUMBER 15- 185-22,314-0000

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

E/2 W/2 SW, SEC. 30, T 24 S, R 14 W/E
1320 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6030

Lease Name Hyter Well # 1

Operator: Ainsworth Operating Company

County Stafford 138.45

Name & Address P. O. Box 1269

Well Total Depth 4260 Viola feet

Colorado Springs, CO 80901

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 384

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allen Drilling Company License Number 5418

Address P. O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 12:00 pm Day: 1 Month: December Year: 1985

Plugging proposal received from Craig Christopher

(company name) Allen (phone) 316-793-5681

were: to fill hole with heavy mud and spot cement through drill pipe Elevation N/A
Anhydrite 955'

1st plug in the Arbuckle with 50 sx cement if in 50' or more

2nd plug at the base of the Anhydrite with 50 sx cement

3rd plug at 420' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement
Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:15 pm Day: 1 Month: December Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 970' with 50 sx cement, 2nd plug at 420' with 50 sx cement

3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement,

5th plug to circulate rat hole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging, RECEIVED STATE CORPORATION COMMISSION

Signed Richard W. Lacey (TECHNICIAN)

DATE DEC 16 1985

DEC 5 1985

INV. NO. 11516

CONSERVATION DIVISION

12-5-85

FORM CP-2/3 Rev. 01-84