

7-12-88

1 051070 (A)

API NUMBER 15- 185-20,711-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

RECEIVED
CONSERVATION DIVISION
Wichita, Kansas

JUL 21 1988

SE SE SE, SEC. 30, T 24 S, R 14 W/E

TECHNICIAN'S PLUGGING REPORT

330 feet from S section line
330 feet from E section line

Operator License # 3646

CONSERVATION DIVISION
Wichita, Kansas

Lease Name Waters Well # 1

Operator: Haven Energy Corporation
Name:
Address: 7310 East Kellogg
Wichita, KS 67207-1695

County Stafford 142.06

Well Total Depth 4371 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 290

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 12 Month: 7 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2474

were: 5 1/2" at 4369' Perfs at 4369-71'

1st plug sand back to 4320' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 a.m. Day: 12 Month: 7 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4320' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 100 sx cement.

Maximum pressure 575 psi and shut in 525 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2800' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
(if desired) observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

DATE 7-26-88

INV. NO. 21655