

To: 1 120556 4-17
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19- 185-20,909-0000 336R
SW SE SE, SEC. 30, T. 24 S, R. 14 W/EX
330 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9354
Operator: Central Energy Corporation
Name & Address P.O. Box 47590
Wichita, KS 67201

Lease Name Waters Well # 2
County Stafford 141.70
Well Total Depth 4360 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8" feet 300

Abandoned Oil Well Gas Well Input Well _____ SHD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 17 Month: 4 Year: 19 91

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4359.5' w/175 sx cement, PBSD 4170', Perfs at 4104-4114'
1st plug sand back to 4000' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by _____ Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 17 Month: 4 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" back to 4000' and dumped 5 sx cement on top
of sand through bailer,

2nd plug pumped 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
released 8 5/8" wiper plug and pumped 125 sx cement down 8 5/8".

Maximum pressure 850 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2201' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-29-91

INV. NO. 31687

Signed D. Crawshaw
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS

4-24-91 APR 24 1991