

1041365

TO: STATE CORPORATION COMMISSION  
API NUMBER 15-185-22,951-0000  
150'S C SE SW SEC. 30, T 24 S, R 14 W

8-13

CONSERVATION DIVISION - PLUGGING SECTION 510 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME HYTER WELL # 3

TECHNICIAN'S PLUGGING REPORT COUNTY STAFFORD

OPERATOR LICENSE # 9482 WELL TOTAL DEPTH 4530 FEET

OPERATOR: NATIONAL PETROLEUM RESERVES PRODUCTION CSG: SIZE 5 1/2" @ 4530' WITH NA SX

NAME AND 260 N ROCK RD, SUITE 130 SURFACE CASING: SIZE 8 5/8" @ 315' WITH NA SX

ADDRESS WICHITA, KS 67206-2241

ABANDONED OIL WELL X GAS WELL        INPUT WELL D=26,895 INJ WELL        D/A       

OTHER WELL AS HEREINAFTER INDICATED       

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31528

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 4:15 PM DAY: 13 MONTH: 08 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM TED FUCHS W/SWIFT SERVICES

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 4370-74

SANDED BACK TO 4320' AND PUT 5 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER. PUMPED DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - & 125 SX CEMENT. MAXIMUM PRESSURE @ 600#. SHUT IN WITH 150#.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART        NONE       

OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 13 MONTH: 08 YEAR: 1999

ACTUAL PLUGGING REPORT       

SANDED BACK TO 4320' AND PUT 5 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER. PUMPED DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG & 125 SX CEMENT. MAXIMUM PRESSURE AT 600#. SHUT IN WITH 150#.

STATE CORPORATION COMMISSION

10-30-99 AUG 30 1999

CONSERVATION DIVISION  
Wichita, Kansas

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. RECOVERED 2000' OF 5 1/2" CASING.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DAD) OBSERVE THIS PLUGGING.

DATE 8-31-99

WV. NO. 60447

SIGNED Stephen J. Pfeifer  
(TECHNICIAN) FORM CP/2/3