

To: 1041003
STATE CORPORATION COMMISSION
Wichita State Office Bldg.
130 S. Market, Room 2078
Wichita, KS 67202

9-25

API NUMBER 15- 185-22,700-0000
S/2 SW SW, SEC. 30, T 24 S, R 14 W/E
330 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9482
Operator: National Petroleum Reserves, Inc.
Name & Address: 250 N. Rock Rd., Ste. 340
Wichita, KS 67206

Lease Name Hyter Well # 1
County Stafford 142.38
Well Total Depth 4381 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 292

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address: P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 25 Month: 9 Year: 19 95

Plugging proposal received from Darrell Kelso
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

work: 5 1/2" at 4370' w/120 sx cement, Open hole 4370-81'
1st plug sand back to 4320' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 2:45 p.m. Day: 25 Month: 9 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4320' and dumped 5 sx cement on top of sand
bridge through bailer.
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.
Maximum pressure 500 psi and shut in 100 psi.

9-28-95

Remarks: Used 65/35 Pozmix 6% gel by Halliburton. Recovered 2000' of 5 1/2" casing.
(If additional descriptive necessity, use BACK of this form.)
I hereby observe this plugging.

SEP 28 1995

Signed [Signature] (TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 10-9-95
INV. NO. 43707