

To: 1. 052072
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 075-20,611-0000
SW NE NE, SEC. 17, T 24 S, R 40 W/E
1250 feet from ~~N~~ section line
980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 4894
Operator: Horseshoe Operating, Inc.
Name:
Address 500 W. Texas, Ste. 1190
Midland, TX 79701

Lease Name Schwieterman Well / 1
County Hamilton 76.79
Well Total Depth 2363 feet
Conductor Pipe: Size - feet
Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 30606
Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: _____ Day: 6 Month: 10 Year: 19 96

Plugging proposal received from Terry Maxwell
(company name) Horseshoe Operating, Inc. (phone) 316-624-6405

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1821'
1st plug at 1850' with 50 sx cement, 2nd plug at 650' with 80 sx cement,
3rd plug at 280' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 4:30 a.m. Day: 6 Month: 10 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 1850' with 50 sx cement,
2nd plug at 650' with 80 sx cement,
3rd plug at 280' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Dowell.
(If additional description is necessary, use BACK of this form.)

Next (if different) observe this plugging.

INVOICED
DATE OCT 17 1996
INV. NO. 46706
10-6

Signed Richard W. Lacey
(TECHNICIAN)

10-15-96
RECEIVED
MURFAS DRILLING COMPANY
NOV 01 1996
P 1:09

EFFECTIVE DATE: 10-2-96

State of Kansas 15-075-20,611-0000

FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

DISTRICT # 1
SSA? Yes No

NOTICE OF INTENTION TO DRILL
Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date 9 1 96
month day year

Spot NE SW - NE - NW Sec 17 Twp 24 S, Rg 40 East West

OPERATOR: License # 4894
Name: Horseshoe Operating, Inc.
Address: 500 W. Texas, Suite 1190
City/State/Zip: Midland, Tx 79701
Contact Person: S. L. Suras
Phone: (915) 683-1448

OK
980
FEL

1250 feet from South / North line of Section
1250 feet from East / West line of Section
SECTION X REGULAR IRREGULAR

CONTRACTOR: License # 30606
Name: Murfin Drilling Company

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Hamilton
Lease Name: Schwietzman Well #: 1
Field Name: Bradshaw
Is this a Prorated Spaced Field? X yes no
Target Formation(s): Winfield
Nearest lease or unit boundary: 280'
Ground Surface Elevation: 3215.5 feet MSL
Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no
Depth to bottom of fresh water: 200'
Depth to bottom of usable water: 200'
Surface Pipe by Alternate: 1 X 350'
Length of Surface Pipe Planned to be set: 350'
Length of Conductor pipe required: _____
Projected Total Depth: 3000'
Formation at Total Depth: Winfield
Water Source for Drilling Operations: _____ well _____ farm pond _____ other

Well Drilled For: Well Class: Type Equipment:
Oil Enh Rec Infield Mud Rotary
X Gas Storage Pool Ext. Air Rotary
GWO Disposal Wildcat Cable
Seismic # of Holes Other
If GWO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth: _____
Bottom Hole Location: _____

Will Cores Be Taken? yes X no
If yes, proposed zone: _____

W.L.E. 194,489-C (C-27,968)
220' Alt. II Req.

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher Terry Maxwell

SPUD DATE 10-3-96 INIT. ~~SM~~

LENGTH SURFACE PLANNED 250'

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2" @ 253 CONDUCTOR
ANHYDRITE T- 1821 B- ELEVATION

TD 2363 FORMATION
RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N

Arbuckle Plug @ Ft. W/ SX

Hug./Council @ Ft. W/ SX

Anhydrite Base @ 1850 Ft. W/ 50 SX

1/2 Base Anyh. @ Ft. W/ SX

1/2, 1/2 Plug @ 650 Ft. W/ 80 SX

Bottom Surface @ 280 Ft. W/ 40 SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 10 SX MOUSE HOLE W/ 10 SX

WATER WELL SX (Irr. Well Pond Hauling)

TECHNICIAN DATE

TYPE OF CEMENT 60/40 690 1/4 # placed

STARTING TIME : (AM/PM) DATE

COMPLETION TIME 4:30AM/PM DATE 10-6

CEMENT COMPANY Dawsel

RECEIVED
KANSAS CORP
COMM