

API NUMBER 15- Comp. 10-1-64

To: 1 020012
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NE NE, SEC. 3, T 24 S, R 41 (W) EX

4620 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8098

Lease Name Boltz Well # A-1 (SWD)

Operator: Damson Oil Corporation

County Hamilton 37.60

Name & Address P. O. Box 750

Well Total Depth 1157 feet

Amarillo, TX 79105

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 699

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well x D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Damson Oil Corporation License Number 8098

Address P. O. Box 750, Amarillo, TX 79105

Company to plug at: Hour: 4:30 pm Day: 2 Month: April Year: 19 86

Plugging proposal received from Gary Moore

(company name) Damson (phone) 303-336-7139

were: 2 3/8" at 1157' PBTD 1086' Perfs at 917-929'; 935-940'; 945-952'

1st plug pump 4 bbls 9# mud with Lost Circulation Material to displace fluid in casing (tubing) and bridge off formation.

2nd plug pump 25 sx cement down casing (tubing) and attempt to load casing.

3rd plug Load casing to within 3' of surface.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4:50 pm Day: 2 Month: April Year: 19 86

ACTUAL PLUGGING REPORT Pump 3 bbls jel water 1/2 sack hulls 5 bbls of heavy cement slurry

top to bottom. Pressured pu at 750psi and let set 4 minutes with pressure of 300 psi.

Cemented to surface. Cut off and welded on cap. App. 2 bbls over displacement tubing.

RECEIVED
STATE CORPORATION COMMISSION

4-13-85 APR 13 1986

Remarks: No recovery. Cemented by Halliburton.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE APR 15 1986

INV. NO. 13403

Signed Glenn Barlow
(TECHNICIAN)