

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20377-00-00
Spot: N2NESE Sec/Twnshp/Rge: 6-24S-41W
2300 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: TATE Well Number: 1-6
County: HAMILTON Total Vertical Depth: 2351 feet

Operator License No.: 8671
Op Name: TATE EXPLORATION
Address: PO BOX 69 101 N. MAIN
LAKIN, KS 67860

Conductor Pipe: Size feet: 376.41
Surface Casing: Size 8.625 feet: 365 WITH 275 SX CMT
Production: Size 4.5 feet: 2350 WITH 550 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 03/20/2002 11:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: CMT CIRCULATED TO SURFACE. PUMP 400# HULLS - 25SX CMT - GEL TO 1000'. PUMP CMT FROM 1000' TO 0'.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/20/2002 1:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2350'. PERFS AT 2289-98'. 4 1/2" CEMENTED TO SURFACE. PUMPED DOWN 4 1/2" CASING 100# HULLS, 20 SX CMT, MUD SPACER 14.7 BBL & 70 SX CMT. HAD CMT FROM 980' TO 0'. MAXIMUM PRESSURE 1000#. SHUT IN AT 1000#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 25 SX CMT. MAXIMUM PRESSURE 300#. SHUT IN AT 200#.

RECEIVED
' MAR 29 2002
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Kevin D Strube
(TECHNICIAN)

INVOICED MAR 26 2002
DATE March 29-02
WIZ. NO. 2002061592 MD

FORM CR-2/3