

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-21254-00-00
Spot: NWNESENW Sec/Twnshp/Rge: 36-34S-2E
3630 feet from S Section Line, 3020 feet from E Section Line
Lease/Unit Name: AIRPORT(JB) Well Number: 1
County: SUMNER Total Vertical Depth: 900 feet

Operator License No.: 32074
Op Name: GREAT BASIN PETROLEUM, INC.
Address: 10 WEST 100 SO. STE 425
SALT LAKE CITY, UT 84101

Conductor Pipe: Size feet:
Surface Casing: Size feet:
Production: Size 2.875 feet: 780 UNKNOWN
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 01/15/2001 11:45 AM
Plug Co. License No.: 3097 Plug Co. Name: K W OIL WELL SERVICE, INC.
Proposal Rcvd. from: JIM KEPLY Company: KW OIL WELL SERVICE Phone: (316) 431-2285

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DAVE WERTZ Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/15/2001 11:45 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

On 1-13-01 thru 1" tubing 780' pumped cement to 250' pulled 1" from well bore. Perforated @ 250', would'nt circulate perforated @ 150' and 75'. Ran poly to 300' inside 2 7/8 and circulated cement to surface.

THIS IS A KCC FEE FUND PLUGGING.

RECEIVED
KCC DISTRICT #2

JAN 18 2001

WICHITA, KS

Remarks: 60/40 2% WW PRODUCTION CONTROL # 20010018-002

Plugged through: TBG

District: 02

Signed


(TECHNICIAN)