

2060114

15-055-19562-000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- OLD Well
C N W N W
SW., SEC. 31, T. 33S, R. 6 #1E
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5-393
Operator: A. L. Abercrombie, Inc.
Name & Address: 801 Union Center
Wichita, ks 67042

Lease Name Hart B Well # 6 SWD
County Cowley
Well Total Depth 2409 78.29 feet
~~Conductor~~ Pipe: Size 5 1/2 feet 2350
Surface Casing: Size 8 5/8 feet 85'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____
Other well as hereinafter indicated _____

Plugging Contractor B & S Well Ser License Number 6013
Address 608 W 8th Winfield ks.

Company to plug at: Hour: _____ Day: 7 Month: 7 Year: 19 84

Plugging proposal received from Ed. Abercrombie
(company name) above (phone) _____

* were: Tubing parted with fish on top approx 2100' - 5 1/2 casing cemented all.
7-7-84 Run 2" tubing to approx 2100' & pump 50 sacks cement. Set
set till 7-9-84 Tag cement & full 5 1/2" full to surface thru 2" tubing.

RECEIVED
STATE CORPORATION COMMISSION
7-17-84
JUL 17 1984

Plugging Proposal Received by T. Wilson
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____
Wichita, Kansas
Operations Completed: Hour: 12:30 PM Day: 9 Month: 7 Year: 19 84

ACTUAL PLUGGING REPORT

9-7-84 Run 2" tubing to 2040' & limited cementing spotted
2 Gels - 1 hulls & 50 sacks Com Cement 3 1/2". Set Set (9-7-84) & Tag Cement
with 2" @ approx 1565' Circulated 125 sacks 60/40 Ptz 3 1/2 cc. Some circulation
of fluid outside 5 1/2" even tho had been cemented. - Pulled tubing pressured up 5 1/2"
to 200' & held 30'. Ran 2" Push to cement & Circulated 125 sacks 60/40 Ptz 3 1/2 cc
to surface. Pulled tubing hooked to 5 1/2" pressured to 500' held 30' full circula
Remarks stopped - shut in casing @ 500' P ST.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-25-84 7640
INV. NO. 2649
7-9

Signed T. Wilson
(TECHNICIAN)

AUG 2 1984

FORM CP-2/3
Rev. 01-84