

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00018-00-01 Spot: CNWE
Sec: 35 Twnshp & Dir: 30 S Rng & Dir: 8 W
Feet: 1980 frm N/S: S Feet: 1980 frm E/W: E
Lease/Unit Name: AHLF A (OWWO) Well Number: 2
County: KINGMAN Total Vertical Depth: 4502 feet

Operator License No.: 6236
Operator Name: M.T.M. Petroleum
Address: PO Box 82
Spivey, KS 67142

6/16

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 160 146.32
Production: Size 5.5 feet: 4496

Well Type: OG UIC Docket No: Date/Time to Plug:

Plug Co. License No.: 31925 Plug Co. Name: Quality Well Service, Inc.

Proposal Received from: Richard McIntyre Company Name: Quality Well Service

OpRepPhoneNo: (316) 278-2476

Were: Perfs. 4424-4426 4390-4394. Sand back above the perfs., and cap with 5sxs of cement. 35sx@1300'. 35sxs@800'. Circulate cement from 250'-0'.

Plugging Proposal Received By: Jack Luthi WitnessType: Plugging Operations Partially Witnessed

Date/Time Plugging Completed: 06/16/2000 12:45 PM

Actual Plugging Report:

The perfs were covered with sand from TD to 4340' and capped w/5sxs of cement. The 5 1/2 was recovered from 1954' and pulled to 1300', 35sxs of cement was spotted. The pipe was pulled to 800', where 35sxs of cement was spotted. The pipe was pulled to 250', where cement was circulated to surface. The remaining pipe was pulled and the cement was brought back to surface.

RECEIVED
KCC DISTRICT #2
JUN 20 2000
6-20-00
WICHITA, KS

Remarks: United Cementing #2830 60/40 4%gel

Anhydrite Plug: No BottomPlug: DakotaPlug: No

Plugged through:

(did) / did not) observe this plugging.

INVOICED
Signed [Signature]

DATE 6/21/00
INVOICE NO. 61890

(TECHNICIAN)

R
Form CP-2/3