

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 3 1967

7-3-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued May 8, 1967.

Operator's Full Name Pan American Petroleum Corporation

Complete Address P. O. Box 432, Liberal, Kansas 67901

Lease Name C. J. Boyle "L" Well No. # 1

Location C SW NW Sec. 35 Twp. 30 Rge. 8 (E) (W) W

County Kingman Total Depth 4500'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Company

Address Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 12:00 P.M. Day 27th Month June Year 1967

The above well was plugged as follows:

198' of 8 5/8" surface pipe, cemented with 250 sacks. 4499' of 5 1/2" long
string, cemented with 250 sacks. Plug back T.D. 4462'. Top perforation 4368'.
Bottom of the hole was sanded to 4350', and cemented with 5 sacks, through
the dump bailer. 3287' of 5 1/2" long string was recovered from the hole. Hole
was filled with mud to 240', rock bridge from 240' to 220', and hole was
with 5 yards of ready-mix cement from 220' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Dickie Elving
Well Plugging Supervisor

DATE 7/3/67
INV. NO. 5515-a