

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-047-20972 RECEIVED
STATE CORPORATION COMMISSION

200 Colorado Derby Building
Wichita, KS 67202

DEC - 8 1981 12-8-81

Operator's Full Name F. G. Holl CONSERVATION DIVISION
Wichita Kansas

Complete Address 6427 East Kellogg Wichita, Kansas 67207

Lease Name Nipon Well No. 3-8

Location 330' 5L-1320' FEL of NE 1/4 Sec. 8 Twp. 24S Rge. 17W (East) (West)

County Edwards Total Depth 4510'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Sterling Drilling Co.

Address Box 129 Sterling Kansas 67579 License No. _____

Operation Completed: Hour: 9:30 AM Day: 3 Month: December Year: 1981

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

There is 254' of 8 1/8" surface casing cemented with 210 lbs cement.
The annular was from 1169' to 1189'. The cedar hill was topped at
800'. 1st plug at 1160' with 50 lbs of cement. 2nd plug on
solid bridge at 840' with 50 lbs of cement. 3rd plug pushed
under plug to 240' with 25 lbs of cement on top of it. 4th plug
40' to 0' on solid bridge with 10 lbs of cement. They pumped
5 lbs of cement in rat hole & 2 lbs of cement in mouse hole
The plugging was accomplished by Halliburton Co.
out of Perth News.

I hereby certify that the above plugging instructions were given as herein stated.

INVOICED

Signed: Paul Luttie
Conservation Division Agent

DATE 1-9-82
INV. NO. 8910-W