

15-095-01512-00-01

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAR 26 1964
3-26-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Leben Drilling Inc.

Complete Address: 905 Central Bldg., Wichita, Kansas

Lease Name Donner Well No. # 1

Location NW NE SW Sec. 36 Twp. 30 Rge. 8 (E) (W) W

County Kingman Total Depth 4485

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole was a wash down

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 12:30PM Day 24th Month March Year 1964

The Above well was plugged as follows:

500' of 8 5/8" surface pipe, cement circulated. 4485' of 5 1/2" long
string, cemented with 175 sacks. Plug back to 4484'. Top perferation
3724'. Bottom of hole was sanded to 3700', and cemented with 5 sacks.
Hole was filled with mud to 275', with 10' rock bridge, and cemented
with 25 sacks. Hole was filled with mud to 40', with 10' rock bridge,
and cemented with 10 sacks to base cellar.
3515' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/26/64
INV. NO. 8848-W

Signed: Archie Elving
Well Plugging Supervisor