

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR Tate Exploration

API NO. 15-075-20,377-0000

ADDRESS Box 69

COUNTY Hamilton

Lakin, Kansas 67860

FIELD Bradshaw

**CONTACT PERSON R.L. Higginbottom

PROD. FORMATION

PHONE 316-624-3767

LEASE Tate

PURCHASER Kansas Nebraska Pipeline Co.

WELL NO. 1-6

ADDRESS Box 608

WELL LOCATION

Hastings, NE 68901

2300 Ft. from South Line and

DRILLING Lakin Drilling Company

660 Ft. from East Line of

CONTRACTOR

ADDRESS Box 69

the SE/4 SEC. 6 TWP. 24S RGE. 41W


Lakin, Kansas 67860

WELL PLAT

PLUGGING

CONTRACTOR

ADDRESS



KCC / KGS (Office Use)

TOTAL DEPTH 2350' PBTD

SPUD DATE 3/27/81 DATE COMPLETED 4/18/81

ELEV: GR 3268' DF -- KB 3275'

DRILLED WITH (XXX) (ROTARY) (XXX) TOOLS

Amount of surface pipe set and cemented 374' DV Tool Used? --

A F F I D A V I T

STATE OF Kansas, COUNTY OF Seward SS, I,

R. L. Higginbottom OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS Agent (FOR) Tate Exploration

OPERATOR OF THE Tate LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1-6 ON

SAID LEASE, HAS BEEN COMPLETED ON THE 18 DAY OF April, 19 81, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIRMED

RECEIVED STATE CORPORATION COMMISSION WICHITA, KANSAS 3 1982 5-3-82

(S) R. L. Higginbottom

SUBSCRIBED AND SWORN BEFORE ME THIS 30th DAY OF April, 19 82

NOTARY PUBLIC - State of Kansas A. J. PARNELL My Appt. Exp. 7-7-85

A. J. Parnell NOTARY PUBLIC

MY COMMISSION EXPIRES:

**The person who can be reached by phone regarding any questions concerning this information. Within 45 days of completion, a witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

SIDE TWO

WELL LOG

Show all important zones of porosity and contents thereof; corad intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Top Winfield (Gas & Water)	2281	2302	Base Stone Corral Top Wfld.	1798 (+1477)
Top Lower Winfield (Water)	2302	did not drill thru		2281 (+994)
Top Stone Corral (Anhydrite)	1780	1798		
No DST. No Cores.				

Report of all strings set— surface, intermediate, production, etc. **CASING RECORD** (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12 1/4"	8-5/8"	20	374'	Class "H"	275	3% CaCl 1/4#/sx D-29
Production	7-7/8"	4 1/2"	9.50	2350'	Halliburton Lite 400 Class "H"	150	18% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval
None			1	Jet - .441"	2289-98

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8"	2316'	None

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gal. 15% acid	2289-98
15,000 gal. KCl water - 20,000# 20/40 sand	2289-98

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
9/22/81	Pump	

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	None	106 bbls.	% -96	bbls.

Disposition of gas (vented, used on lease or sold)

SI Gas Well

Perforations