

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-185-20546-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR F. G. HOLL COMPANY OPERATORS LICENSE NO. 5056

ADDRESS 6427 East Kellogg, Wichita, KS 67207 PHONE # (316) 684-8481

P. O. Box 780167

LEASE (FARM) Loder WELL NO. 1 WELL LOCATION C NW SW COUNTY Stafford

SEC. 30 TWP. 24 RGE. 15W (E) or (W) TOTAL DEPTH 4350 PLUG BACK TD 4305

Check One:

OIL WELL _____ GAS WELL X D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 250' CEMENTED WITH 235 SACKS

CASING SIZE 4 1/2" SET AT 4349' CEMENTED WITH 135 SACKS

PERFORATED AT 4256 - 4272 Re-Perf at 4256 - 4262

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL _____

Heavy Mud, Hulls, Cement and Halliburton Plug

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACC-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN As soon as possible

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Art Merrick

PHONE # (316) 995-3171

ADDRESS P. O. Box 158, Belpre, KS 67519

PLUGGING CONTRACTOR Kelso Casing Pulling

LICENSE NO. 6050

ADDRESS Box 347, Chase KS 67524

PHONE # (316) 938-2457

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT

SIGNED: Elwyn H. Nagel
(Operator or Agent)

Elwyn H. Nagel, Manager

DATE: 5-29-90

MAY 29 1990

CONSERVATION DIVISION
Wichita, Kansas

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- AMIDON LODER #1
Located: C NW SW, Section 30-24S-15W, Stafford County,
Kansas

OWNER: F. G. Holl, Barton A. Holl, Sterling Drilling Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 1, 1974
COMPLETED: November 10, 1974

TOTAL DEPTH: 4350'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 135 Sand and Clay	Ran 6 joints used 8 5/8" casing, 238' cemented at 250' K.B. with 235 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 4:30 AM, November 2, 1974.
135 - 255 Shale	
255 - 400 Shale and Sand	
400 - 1038 Red Bed and Sand	Ran 138 joints 4 1/2", 8rd, 10.5#, Rge 2, new casing, 4353' set at 4349 K.B. with 35 sacks Howco Lite, followed with 100 sacks Pozmix, 18% salt. Plug down at 10:15 AM, November 10, 1974.
1038 - 1057 Anhydrite	
1057 - 1295 Shale	
1295 - 1860 Shale with Lime Stringers	
1860 - 3845 Shale and Lime	
3845 - 4305 Lime	
4305 - 4340 Shale and Sand	
4340 - 4350 Lime	

RECEIVED
STATE CONSERVATION COMMISSION

MAY 29 1990

CONSERVATION DIVISION
Wichita, Kansas



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE

OCT 10 1990

EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

July 10, 1990

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

F. G. Holl Company
6427 E. Kellogg
P.O. Box 780167
Wichita, KS 67207

Loder 1
C NW SW
Sec. 30-24-15W
Stafford County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
Shari Feist Albrecht
Director

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-670