

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-21828-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 36-30S-8W  
3630 feet from S Section Line, 4290 feet from E Section Line  
Lease/Unit Name: BOYLE/HILLS Well Number: 3  
County: KINGMAN Total Vertical Depth: 4456 feet

Operator License No.: 6236  
Op Name: M.T.M. PETROLEUM  
Address: PO BOX 82  
SPIVEY, KS 67142

Conductor Pipe: Size feet: 9/44.82  
Surface Casing: Size 8.625 feet: 220 185 SX CMT  
Production: Size feet:  
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 11/16/2002 8:00 AM  
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.  
Proposal Rcvd. from: MARVIN A. MILLER Company: M & M Phone: (620) 532-3794

Proposed Plugging Method: 35 SX 1300', 35 SX 850', 40 SX 270', 25 SX 60', RAT HOLE 20 SX, MOUSE HOLE 10 SX.

RECEIVED  
KCC DISTRICT #2  
JAN 27 2003  
1-27-03  
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI  
Date/Time Plugging Completed: 11/16/2002 4:00 PM

WitnessType: Plugging Operations Were Not Witnessed  
KCC Agent: JACK LUTHI

Actual Plugging Report:


CIRCULATED HEAVY MUDD IN BORE HOLE.--RAN DRILL PIPE TO 1300', PUMPED 35 SX, PULLED TO 850', PUMPED 35 SX, PULLED TO 270', PUMPED 40 SX, PULLED TO 60', CIRCULATED CEMENT TO SURFACE. RAN 2 JOINTS OF PIPE IN THE RAT HOLE AND PUMPED 20 SX ALSO IN THE MOUSE HOLE AND PUMPED 10 SX.

Remarks: ALLIED #88526 60/40 4%

Plugged through: DP

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE 2-3-03

INV. NO. 2003061144