

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-047-21293-0000

LEASE NAME Breensing B

WELL NUMBER 8-12

3795 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 12 TWP. 24 RGE. 17 (X) or (W)

COUNTY Edwards

Date Well Completed 10-20-87

Plugging Commenced 3:10 pm

Plugging Completed 4:10pm

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR F. G. Holl

ADDRESS 6427 East Kellogg
P. O. Box 780167

PHONE#(316) Wichita, Kansas 67278-0167
684-8481 OPERATORS LICENSE NO. 5056

Character of Well D&A

(Oil, Gas, D&A SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? District #1

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS		CASING RECORD				
Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	309'	225 sacks

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Filled hole with heavy mud with 50 sacks at 1180' through open ended drill pipe with 50 sacks. Plug at 330', 10 sacks at 40' to surface, 15 sacks in rathole, 60-40 Pozmix 6% Cel. B.J. Titan

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address PO Box 129, Sterling, Kansas 67579

STATE OF Kansas COUNTY OF Rice, ss.

Richard L. Mead (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Richard L Mead

(Address) PO Box 129, Sterling, Ks 67579

SUBSCRIBED AND SWORN TO before me this 22 day of October, 19 87

NOV 2 1987
 F. A. WUELLNER
 Notary Public F. A. Wuellner
 My Comm. Expires: _____

My Commission Expires: _____

September 17, 1989

11-2-87

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- -Brensing B 8-12

Located: 30' East of N/2 NE SW NW, Section
12-T24S-R17W, Edwards County, Ks.

OWNER: F. G. Holl Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company
COMMENCED: October 15, 1987
COMPLETED: October 20, 1987
TOTAL DEPTH: 4410'

LOG

0' - 75' Surface soil and sand
75' - 313' Clay and Shale
313' - 1114' Shale
1114' - 1133' Anhydrite
1133' - 4410' Shale and lime

CASING RECORD

Ran 7 joints 8 5/8" 24# new casing. 295.12' pipe set at 309' KB. Cemented with 225 sacks 60-40 Pozmix, 2% Gel, 3% cc. Plug down at 12:45 PM 10-15-87 by B.J. Titan. Good returns.

Plugged

DEVIATION SURVEYS:

1° at 2144'
1° at 4410'

RECEIVED
STATE CORPORATION COMMISSION

NOV 2 1987

CONSERVATION DIVISION
Wichita, Kansas