

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-21,344-0000

LEASE NAME Brensing

WELL NUMBER B #9-12

4950 Ft. from S Section Line

3960' Ft. from E Section Line

SEC. 12 TWP. 24 RGE. 17 (X) or (W)

COUNTY Edwards

Date Well Completed 8-24-89

Plugging Commenced 8-24-89 3:45PM

Plugging Completed 8-24-89 5:00PM

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F. G. Holl Company

ADDRESS P. O. Box 780167 Wichita, Kansas 67278-0167

PHONE#(316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-23-89 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ if not, Is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4442'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	305	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Filled hole with heavy mud, plugged with 50 sacks at 1130'; 40 sacks at 350'; 10 sacks at 50' to surface; 15 sacks in rathole. Used 60/40 Pozmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P O Box 129, Strling, Kansas 67579

STATE OF Kansas COUNTY OF Rice, ss.

Harry J. Mead, Vice President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Harry J. Mead

Harry J. Mead, Vice President

(Address) PO Box 129, Sterling, Kansas 67579

8-28-89

Subscribed and sworn to before me this 25 day of August, 19 89

F. A. Wuellner

Notary Public F.A. Wuellner

My Commission Expires: \_\_\_\_\_

RECEIVED  
STATE OF KANSAS  
AUG 28 1989  
CONSERVATION DIVISION  
Wichita, Kansas



# STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG -----Brensing B #9-12  
Located N/2 N/2 NW, Section 12-T24S-R17W, Edwards County,  
Kansas.

OWNER: F. G. Holl Estate  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: August 18, 1989  
COMPLETED: August 24, 1989

TOTAL DEPTH: 4442'

<u>Log</u>	
0 - 150	Sand & clay
150 - 323	Shale & Red Beds
323 - 1110	Shale & Red Beds
1110 - 1130	Anyhdrite
1130 - 4442	Lime & Shale

Casing record

Ran 7 joints 8 5/8" 23# new casing.  
305.02' pipe set at 320' KB. Cemented  
with 225 sacks 60/40 Pozmix, 2% Gel,  
3% cc. Plug down at 1:45PM by Howco  
8-18-89

Plugged 8-24-89

RECEIVED  
STATE OF KANSAS  
AUG 28 1989  
CONSERVATION DIVISION  
Wichita, Kansas

DEVIATION SURVEY

1° at 4305'