

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-21,378-0000

LEASE NAME Greene

WELL NUMBER A 1-8

3960 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 8 TWP. 24S RGE. 17WE or (W)

COUNTY Edwards

Date Well Completed May 12, 1991

Plugging Commenced 12:30AM 5-12-91

Plugging Completed 2:00 AM 5-12-91

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F. G. Holl company

ADDRESS PO Box 780167, Wichita, Kansas 67278-0167

PHONE#(316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well dry hole

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 6, 1991 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	313'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Filled hole with heavy mud, 50 sacks at 1190', 50 sacks at 600', 40 sacks at 350', 15 sacks 60' to surface, 15 sacks in rathole. 60/40 Pozmix W/ 6% gel. By BJ Titan. Sterling Drilling Co. witness Vaughn Thompson - State pluggger was not present.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address PO Box 129

STATE OF Kansas COUNTY OF Rice, ss.

Richard L. Mead - Agent (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED  
STATE CORPORATION COMMISSION


(Signature) Richard L. Mead  
Richard L. Mead - Agent  
(Address) PO Box 129, Sterling, Ks 67579

5-14-91

SUBSCRIBED AND SWORN TO before me this 12 day of May, 19 91

CONSERVATION DIVISION  
Wichita, Kansas

My Commission Expires: \_\_\_\_\_



F. A. Wuellner  
Notary Public F. A. Wuellner

## STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

SAMPLE LOG ----- Greene A #1-8  
 E/2, E/2, NW/4, Section 8-T24S-R17W, Edwards Co., Ks.

OWNER - F. G. Holl Family Trust  
 ROTARY DRILLING CONTRACTOR - Sterling Drilling company

DATE COMMENCED - May 4, 1991

DATE COMPLETED - May 11, 1991

TOTAL DEPTH 4520' DTD  
 4516' LTD

## - LOG -

0 - 90'	Surface soil & sand
90 - 315'	Red bed & Shale
315 - 1172'	Lime & shale
1172 - 1190'	Anhydrite
1190 - 4520'	Lime & shale

## Casing Record

Spud at 5:00 PM 5-4-91. Drilled 315'  
 12 1/4" hole. Ran 7 joints 8 5/8" 23#  
 new casing. 300.28' pipe set at 313'  
 KB. Cemented with 225 sacks 60/40 Pozmix  
 W/ 2% gel & 3% cc. Plug down at 10:30  
 PM 5-4-91 by BJ Titan. Good returns  
 to surface

Plugged

deviation surveys

4380' 3/4°

RECEIVED  
 STATE CORPORATION COMMISSION

MAY 14 1991

CONSERVATION DIVISION  
 Wichita, Kansas