

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Edwards SEC. 8 TWP. 24S RGE. 17W E/W
Location as in quarters or footage from lines:
330' FSL; 1320' FEL, NE/4

Lease Owner F. G. Hill
Lease Name Nixon #3-8 Well No. 3-8
Office Address P. O. Box 129, Sterling, Kansas 67579
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed December 3, 1981
Application for plugging filed December 3, 1981
Plugging commenced 7:45 AM December 3, 1981
Plugging completed 9:30 AM December 3, 1981
Reason for abandonment of well or producing formation Dry Hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthie

Producing formation _____ Depth to top _____ bottom T.D. 4510'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	263'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud,
Plugged through open ended drill pipe,
filled hole with heavy mud, 50 sacks 50/50 Pozmix
with 4% gel and 3% cc at 1160'; 50 sacks at 840';
25 sacks with rubber plug at 240'; Bridge, 1/2 sack
hulls, wood plug and 10 sacks at 40'. 5 sacks in
rathole. 2 sacks in water well.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY
(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas
(Address) 67579

SUBSCRIBED AND SWORN TO before me this 4th day of December, 1981.



Agnes D. Wurst
Agnes D. Wurst, Notary Public

My Commission expires: _____

STATE CORPORATION COMMISSION

DEC 11 1981
CONSERVATION DIVISION
Wichita Kansas

12-8-81

STERLING DRILLING COMPANY
 P. O. Box 129
 Sterling, Kansas 67579

WELL LOG - - - - - NIXON #3-8
 Located: 330' FSL; 1320' FEL, NE/4, Section 8-24S-17W,
 Edwards County, Kansas

OWNER: F. G. Holl
 ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 27, 1981
 COMPLETED: December 3, 1981

TOTAL DEPTH: 4510'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 71 Surface Soil and Sand	Ran 7 joints 8' 4/8", 24# new casing.
71 - 101 Sand	250.74' pipe set at 263' K.B. Cemented
101 - 266 Shale	with 210 sacks 60/40 Pozmix with 3% cc.
266 - 830 Shale, Sand and Red Bed	Plug down at 6:30 PM, 11-27-81, by Howco.
830 - 1169 Shale and Red Beds.	
1169 - 1189 Anhydrite	
1189 - 1570 Shale	
1570 - 4415 Lime and Shale	
4415 - 4510 Lime, Chert, Shale	Plugged.

3/4° at 2076'
 3/4° at 4415'