

15-047-20674-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Edwards County. Sec. 8 Twp. 24S Rge. 17W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
330' FNL; 530' FEL, NW/4

Lease Owner F. G. Holl
Lease Name Adams-Hilt #1-8 Well No. 1-8
Office Address 6427 East Kellogg, Wichita, Kansas 67207
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed May 16, 1980 19
Application for plugging filed May 15, 1980 19
Application for plugging approved May 15, 1980 19
Plugging commenced 7:00 AM, May 16, 1980 19
Plugging completed 9:30 AM, May 16, 1980 19
Reason for abandonment of well or producing formation _____

Dry Hole
If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4520'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	266'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
Plugged with 40 sacks at 540';
40 sacks at 260'; filled hole with heavy
mud, solid bridge and plug with 10 sacks
a at 40'; 5 sacks in rat hole and 2 sacks
in water well.

5-28-80
RECEIVED
STATE CORPORATION COMMISSION
MAY 28 1980
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY
(Signature) [Signature]
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of May, 19 80.



[Signature]
Charles M. Hall, Notary Public.

My commission expires _____

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - ADAMS-HILT #1-8
Located: 330' FNL; 530' FEL, NW/4, Section 8-24S-17W,
Edwards County, Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 9, 1980
COMPLETED: May 16, 1980

TOTAL DEPTH: 4520'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 80 Surface Soil and Sand	Ran 6 joints used 28#, 8 5/8" casing.
80 - 1208 Shale, Sand, Red Bed	254.41' set at 266 K.B. with 225 Sacks
1208 - 1228 Anhydrite	60/40 Pozmix with 3% cc. Plug down at
1228 - 1465 Shale	1:45 PM, 5-9-80, by Howco.
1465 - 2185 Shale and Shells	
2185 - 4428 Shale and Lime	
4428 - 4463 Chert	
4463 - 4520 Lime and Shale	Plugged.

RECEIVED
STATE CORPORATION COMMISSION

MAY 28 1980

CONSERVATION DIVISION
Wichita, Kansas

Deviation Surveys: 1/2° at 2217'
1° at 4428'