

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-20,742-000

LEASE NAME "Derley"

WELL NUMBER 2-13

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 13 TWP. 24 RGE. 17W (E or W)

COUNTY Edwards

Date Well Completed

Plugging Commenced 7-31-90

Plugging Completed 8-9-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F.G. Holl Company

ADDRESS P.O. Box 158 Belpre, KS. 67519

PHONE#(316) 995-3171 OPERATORS LICENSE NO. 5056

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filled? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 4443'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	285'	none
				4 1/2"	4438'	2108'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom to 4260' dumped 4 sacks cement. Shot pipe @2521',
2404', 2324', 2203', 2108'. Mixed 300# hulls, 10 sacks gel,
50 sacks cement, 10 sacks gel, 100# hulls, 150 sacks cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 14 day of August, 19 90

Gene Herzberg
Notary Public

My Commission Expires:



STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- DERLEY #2-13
Located: C NW SE, Section 13-24S-17W, Edwards County,
Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 25, 1980
COMPLETED: October 1, 1980

TOTAL DEPTH: 4440'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 123 Surface Soil and Sand	Ran 6 joints used 28#, 8 5/8" casing,
123 - 288 Red Beds and Shale	273.07' set at 285' K.B. Cemented
288 - 1113 Shale, Sand, Red Bed	with 225 sacks 60/40 Pozmix with 3%
1113 - 1130 Anhydrite	cc. Plug down at 3:00 PM, 9-25-80,
1130 - 2055 Shale	by Howco.
2055 - 3765 Lime and Shale	
3765 - 3975 Lime	
3975 - 4440 Lime and Shale	Ran 7 joints used 4 1/2" OD casing
	and 115 joints 10.5# new 4 1/2" OD
	casing. 4429.18' set at 4438' K.B.
	with 225 sacks Regular Mix. Plug
	down at 9:30 PM, 10-1-80, by Howco.

Deviation Surveys: 2° at 2260'
1° at 4330'

RECEIVED
STATE GEOLOGICAL COMMISSION

MAY 29 1990

CONSERVATION DIVISION
Wichita, Kansas