

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Edwards SEC. 13 TWP. 24S RGE. 17W N/W
Location as in quarters or footage from lines:
NE SE NW

Locate Well
correctly on above
Section Platt.

Lease Owner F. G. Holl
Lease Name Hawley #7-13 Well No. 7-13
Office Address 6427 East Kellogg, Wichita, Kansas 67207
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed July 13, 1983
Application for plugging filed July 13, 1983
Plugging commenced 4:00 PM, July 13, 1983
Plugging completed 5:30 PM, July 13, 1983
Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation _____ Depth to top _____ bottom T.D. 4410'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	261'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Filled hole with heavy mud.
Heavy mud plugged through open ended drill pipe,
50 sacks at 1080'; 40 sacks at 600'; 40 sacks
at 300'; bridge, 1/2 sack hulls, plug and
10 sacks at 40'. 10 sacks in rathole with joint
of drill pipe; 5 sacks in water well. Used
60/40 Pozmix, 2% gel and 3% cc.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY

(Signature) [Signature]
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas
(Address) 67579



SUBSCRIBED AND SWORN TO before me this 14th day of July, 19 83.

RECEIVED [Signature]
STATE CORPORATION COMMISSION, Wurst, Notary Public.

My Commission expires: 4-6-85

JUL 18 1983

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - HAWLEY #7-13

Located: NE SE NW, Section 13-24S-17W, Edwards County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: July 7, 1983

COMPLETED: July 13, 1983

TOTAL DEPTH: 4410'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Soil and Sand	Ran 6 joints 8 5/8", 24# new casing.
90 - 264 Shale	248.56' pipe set at 261' K.B. Cemented
264 - 990 Shale, Sand, Red Bed	with 210 sacks 60/40 Pozmix plus 3% cc.
990 - 1092 Shale	Plug down at 5:45 PM, 7-7-83, by Howco.
1092 - 1106 Anhydrite	
1106 - 2010 Shale, Lime Stringers	
2070 - 4249 Lime and Shale	
4249 - 4286 Mississippi	
4286 - 4410 Lime and Shale	Plugged.

Deviation Surveys: 1 1/2° at 2264'
1° at 4286'

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1983

CONSERVATION DIVISION
Wichita, Kansas