

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-21,160-0000

LEASE NAME Miller

WELL NUMBER 3-13

SPOT LOCATION NW SW SW

SEC. 13 TWP. 24 SRGE. 17 (~~20~~ (W))

COUNTY Edwards

Date Well Completed 3-23-84

Plugging Commenced 12:30 AM
3-23-84

Plugging Completed 2:15 AM
3-23-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F. G. Holl

ADDRESS 6427 East Kellogg
Wichita, Kansas 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? #1

Is ACO-1 filed? If not, is well log attached? Yes

Producing formation Depth to top bottom T.D. 4495

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	258'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud.

Heavy mud plugged through open ended drill pipe:

50 sacks at 1110'; 70 sacks at 480'; 1/2 sack hulls, plug and 10 sacks at 40'
15 sacks in rathole. Plugged water well with 5 sacks. Used 60/40 Pozmix, 2% gel (4% total)
(If additional description is necessary, use BACK of this form.) and 3% cc.

Name of Plugging Contractor Sterling Drilling Company License No. 5142
Address P. O. Box 129
Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

STERLING DRILLING COMPANY

(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
(Address) P. O. Box 129, Sterling, Ks 67579

RECEIVED
STATE CORPORATION COMMISSION

SUBSCRIBED 1984 SWORN TO before me this 26 day of March, 19 84.

CONSERVATION DIVISION
Wichita, Kansas

Agnes D. Wurst
Agnes D. Wurst - Notary Public



My Commission expires: 4-6-85

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - MILLER #3-13

Located: NW SW SW, Section 13-24S-17W, Edwards County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: March 16, 1984

COMPLETED: March 23, 1984

TOTAL DEPTH: 4495'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Soil and Sand	Ran 6 joints new 8 5/8", 23# casing.
90 - 260 Shale	245.48' pipe set at 258' K.B. Cemented with 200 Sacks 60/40 Pozmix, plus 3% cc. Plug down at 5:30 PM, 3-16-84, by Howco.
260 - 1016 Shale, Sand, Red Bed	
1016 - 1098 Shales	
1098 - 1126 Anhydrite	
1126 - 1576 Shales	
1576 - 4322 Lime and Shale	
4322 - 4350 Chert	
4350 - 4495 Lime and Shale	Plugged.

RECEIVED
STATE CORPORATION COMMISSION

MAR 29 1984

CONSERVATION DIVISION
Wichita, KansasDeviation Surveys: 0° at 2163'
1° at 4350'