


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

STAFFORD County. Sec. 19 Twp. 24S Rge. 15 (X)X (W)
Location as "NE/CNW/SW" or footage from lines. APP. C SW NW
Lease Owner PETROLEUM, INC.,
Lease Name YOUNG Well No. 1-1
Office Address R.R. #2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed JANUARY 29 19.69
Application for plugging filed JANUARY 29 19.69
Application for plugging approved JANUARY 29 19.69
Plugging commenced JANUARY 29 19.69
Plugging completed JANUARY 29 19.69
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONE

If a producing well is abandoned, date of last production. NONE 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well R. J. WARREN
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4370 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	208'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

HEAVY MUD TO 500', FOLLOWED WITH 50 SACKS CEMENT. HEAVY MUD TO 200', FOLLOWED WITH 25 SACKS CEMENT. HEAVY MUD TO 40', FOLLOWED WITH 10 SACKS CEMENT TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION
FEB 5 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GARVEY DRILLING COMPANY
Address R.R. #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
MONTE CHADD (employee of owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.

(Signature) *Monte Chadd*
R.R. #2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 4 day of FEBRUARY, 19 69

My commission expires MAY 28, 1969

Richard N. Dumbler
Notary Public.

WELL LOG

COMPANY Petroleum, Inc.

SEC. 19 T. 24S R. 15W

FARM Young NO. L-1

LOC. SW NW


TOTAL DEPTH 4370'

COUNTY Stafford Co., Kansas

COMM. 1-20-69 COMP. 1-29-69

CONTRACTOR Garvey Drilling Company

CASING : 8 5/8" @ 208' w/175 SX



ELEVATION 2052' KB

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 125' Surface Sand
- 209' Blue Shale
- 900' Shale & Sand
- 1015' Shale
- 1045' Anhydrite
- 2025' Shale
- 3579' Shale & Lime
- 3650' Lime
- 4140' Lime & Shale
- 4248' Lime
- 4300' Lime & Shale
- 4355' Lime
- 4370' Lime & Shale
- 4370' RTD

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 5 1969
 CONSERVATION DIVISION
 Wichita, Kansas

State of Kansas }
 County of Barton } SS

I, Eunice McEachern of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Young L-1 well.

Eunice McEachern

Subscribed and sworn to before me this 31st day of January 19 69

My Commission Expires: November 5th, 1969

Richard D. Doy
 NOTARY PUBLIC